

| SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | |
|-----------------------|--|--------|------------------|----------------------------|--|--|--|-----------------------|--|-------|------------------|----------------------------|--|--|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 85% FEDERAL 15% STATE 0005 | | | | CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 85% FEDERAL 15% STATE 0005 | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 6 | | | | 70300280 | TEMPORARY PAVEMENT MARKING | FOOT | 539 | 539 | | | |
| | | | | | | | | | - LINE 24" | | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SO FT | 22838 | 22838 | | | |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | 1 | | | | * 78000100 | THERMOPLASTIC PAVEMENT MARKING | SO FT | 939 | 939 | | | |
| | | | | | | | | | - LETTERS AND SYMBOLS | | | | | | |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 | | | | * 78000200 | THERMOPLASTIC PAVEMENT MARKING | FOOT | 55343 | 55343 | | | |
| | | | | | | | | | - LINE 4" | | | | | | |
| 70102622 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701502 | L SUM | 1 | 1 | | | | * 78000400 | THERMOPLASTIC PAVEMENT MARKING | FOOT | 2515 | 2515 | | | |
| | | | | | | | | | - LINE 6" | | | | | | |
| 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 11819 | 11819 | | | | * 78000500 | THERMOPLASTIC PAVEMENT MARKING | FOOT | 368 | 368 | | | |
| | | | | | | | | | - LINE 8" | | | | | | |
| 70300210 | TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS | SO FT | 939 | 939 | | | | * 78000600 | THERMOPLASTIC PAVEMENT MARKING | FOOT | 888 | 888 | | | |
| | | | | | | | | | - LINE 12" | | | | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 55343 | 55343 | | | | * 78000650 | THERMOPLASTIC PAVEMENT MARKING | FOOT | 539 | 539 | | | |
| | | | | | | | | | - LINE 24" | | | | | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 2515 | 2515 | | | | * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 685 | 685 | | | |
| | | | | | | | | | | | | | | | |
| 70300250 | TEMPORARY PAVEMENT MARKING - LINE 8" | FOOT | 368 | 368 | | | | 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 685 | 685 | | | |
| | | | | | | | | | | | | | | | |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 888 | 888 | | | | * 88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 1164 | 1164 | | | |
| | | | | | | | | | | | | | | | |
| | * SPECIALTY ITEMS | | | | | | | | | | | | | | |

| | | | |
|--------------------------------|--------------------|------------|-----------|
| FILE NAME * | USER NAME * dupler | DESIGNED - | REVISED - |
| CSW... \work\dupler\024681.dwg | | DRAWN - | REVISED - |
| | | CHECKED - | REVISED - |
| | | DATE - | REVISED - |
| | | | |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TORRENCE AVE. (IL RTE. 83 (GLENWOOD DYER RD.) TO STEGER RD.)
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 2 OF 3 SHEETS STA. TO STA.

| | | | | |
|---|------------------------|----------------|--------------------|----------------|
| F.A.U. RTE. 2937 | SECTION 2010-121-RS | COUNTY COOK | TOTAL SHEETS 32 | SHEET NO. 4 |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | | |
| CONTRACT NO. 60M44 | | | | |