

URBAN

CODE NO.	ITEM	UNIT	STP FUNDING	CONSTRUCTION	
			80% FEDERAL 20% STATE	0005 ROADWAY	0011 SN 045 -0078
TOTAL QUANTITY					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1868	1868	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1962	1962	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1749	1749	
* 70600255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	9	9	
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5006	5006	
Δ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	31	31	
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	291		291
Δ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	37	37	
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1		1
Δ 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
Δ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SO FT	981	981	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	7	7	
Δ * 89000050	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
Δ * X0326276	TEMPORARY LIGHTING FOR SINGLE LANE STAGING	L SUM	1	1	
* X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	142		142
* X4401198	HOT-MIX ASPHALT REMOVAL, VARIABLE DEPTH	SO YD	507	507	
X4810200	AGGREGATE SHOULDER REMOVAL	CU YD	553	553	
* X6650206	WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED	FOOT	393	393	
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
* X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	5228	5228	
* X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	63	63	
* Z0004638	PAVEMENT BREAKING	SO YD	5067	5067	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5
* Z0019600	DUST CONTROL WATERING	UNIT	5	5	
* Z0026407	TEMPORARY SHEET PILING	SO FT	1212		1212
* Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	80	80	
* Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	164		164
* Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	10	10	
* Z0062456	TEMPORARY PAVEMENT	SO YD	288	288	

* SEE SPECIAL PROVISIONS Δ SPECIALTY ITEM

FILE NAME: D:\BENTON\AT-500.dwg
 MODEL: Default
 PLOT DRIVER: vbi_ppc_dwt12.ctb



USER NAME: meann
 PLDT SCALE: 100.0000' / in.
 PLOT DATE: 10/24/2012

DESIGNED - MCV
 DRAWN - CMM
 CHECKED - MTM
 DATE - 10/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE. 326	SECTION 106X-B	COUNTY KANE	TOTAL SHEETS 87	SHEET NO. 4
CONTRACT NO. 60N13				
ILLINOIS FED. AID PROJECT				