

PAVEMENT MARKING SCHEDULE							
SIDE	LOCATION STA	DESCRIPTION	WET REFLECT TEMP TAPE TYPE III, 4"	WET REFLECT TEMP TAPE TYPE III, 24"	THERMO- PLASTIC PAVEMENT MARKING - LINE 4"	THERMO- PLASTIC PAVEMENT MARKING - LINE 24"	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"
			FOOT	FOOT	FOOT	FOOT	FOOT
IL RTE 47							
LT	1454+50.00 TO 1462+22.90	EDGE - WHITE			773		
LT	1462+22.90 TO 1463+51.90	EDGE - WHITE					129
LT	1463+51.90 TO 1471+00.00	EDGE - WHITE			749		
RT	1454+50.00 TO 1462+12.71	EDGE - WHITE			763		
RT	1462+12.71 TO 1463+41.71	EDGE - WHITE					129
RT	1463+41.71 TO 1468+27.99	EDGE - WHITE			487		
RT	1470+19.87 TO 1471+00.00	EDGE - WHITE			81		
CL	1454+50.00 TO 1462+17.81	SKIP - YELLOW			192		
CL	1462+17.81 TO 1463+46.81	SKIP - YELLOW					33
CL	1463+46.81 TO 1468+96.00	SKIP - YELLOW			138		
CL	1454+00.00 TO 1460+91.00	SOLID - YELLOW			691		
CL	1464+91.00 TO 1468+96.00	SOLID - YELLOW			405		
CL	1469+81.00 TO 1471+00.00	DBL - YELLOW			238		
STAGE 1							
	1452+75.00 TO 1473+19.00		2044				
	1460+10.00 TO 1465+50.00		540				
	1456+50.00	STOP BAR		12			
	1469+26.00	STOP BAR		12			
STAGE 3							
	1451+36.00 TO 1473+80.00		2244				
	1460+80.00 TO 1464+80.00		400				
RT	1451+26.00	STOP BAR		12			
LT	1474+30.00	STOP BAR		12			
SILVER GLEN ROAD							
LT	200+12.00 TO 201+25.00	EDGE - WHITE			159		
RT	200+12.00 TO 201+25.00	EDGE - WHITE			164		
CL	200+42.00 TO 201+25.00	DBL - YELLOW			166		
	200+12.00 TO 201+25.00	STOP BAR				31	
STAGE 1							
	200+90.00	STOP BAR		15			
TOTAL			5228	63	5006	31	291

PAVEMENT MARKING REMOVAL SCHEDULE				
SIDE	LOCATION STA	DESCRIPTION	PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL
			SQ FT	SQ FT
IL RTE 47				
STAGE 1				
	1452+75.00 TO 1453+75.00	CL	43	
	1471+75.00 TO 1473+19.00	CL	96	
	1452+75.00 TO 1473+19.00	CL & EDGE		681
	1460+10.00 TO 1465+50.00	CL & EDGE		180
	1456+50.00	STOP BAR		24
	1469+26.00	STOP BAR		24
STAGE 2				
	1473+19.00 TO 1473+70.00	CL	34	
STAGE 3				
	1451+36.00 TO 1452+75.00	CL	63	
	1451+36.00 TO 1473+70.00	EDGE	745	
	1451+36.00 TO 1473+80.00			748
	1460+80.00 TO 1464+80.00			133
RT	1451+26.00	STOP BAR		24
LT	1474+30.00	STOP BAR		24
SILVER GLEN ROAD				
STAGE 1				
LT	200+90.00	STOP BAR		30
TOTAL			981	1868

TEMPORARY CONCRETE BARRIER SCHEDULE		
LOCATION	TEMP CONC BARRIER	RELOCATE TEMP CONC BARRIER
	FOOT	FOOT
STAGE 1		
STA 1453+41.00 TO 1472+09.00	1665	
STAGE 2		
STA 1452+69.00 TO 1455+66.00	297	
STA 1455+66.00 TO 1472+31.00		1665
STAGE 3		
STA 1467+91.00 TO 1468+75.00		84
TOTAL		
	1962	1749

TREE REMOVAL SCHEDULE			
SIDE	LOCATION STA	6 TO 15 UNITS DIAM	OVER 15 UNITS DIAM
		UNIT	UNIT
LT	39'	1457+06.00	6
LT	31'	1463+52.00	6
RT	37'	1455+45.00	8
RT	48'	1462+38.00 (4 @ 12 UNITS EA)	48
RT	40'	1462+50.00 (4 @ 10 UNITS EA)	40
RT	14'	1462+75.00	14
RT	32'	1462+86.00 (4 @ 8 UNITS EA)	32
RT	36'	1455+01.00	24
RT	37'	1462+74.00	16
RT	28'	1465+42.00	30
TOTAL			154
			70

PAVEMENT MARKER SCHEDULE			
LOCATION	RRPM	RRPM (BRIDGE)	RRPM REMOVAL
	EACH	EACH	EACH
STA 1454+50.00 TO STA 1471+00.00	37		
STA 1462+50.00		1	
STAGE 1			
STA 1452+75.00 TO STA 1453+75.00			2
STA 1471+75.00 TO STA 1473+19.00			2
STAGE 2			
STA 1473+19.00 TO STA 1473+70.00			1
STAGE 3			
STA 1451+36.00 TO STA 1452+75.00			2
TOTAL			7

REMOVING AND RESETTING STREET SIGNS SCHEDULE				
SIDE	LOCATION STA	SIGN DESIGNATION	SIGN DESCRIPTION	QTY
				EACH
IL RTE 47				
RT	1459+00.00	W2-2R-3636 WITH SUPP W16-8P-248	SIDE ROAD ADVANCE WARNING	2
RT	1460+91.00	W14-3-646448	NO PASSING ZONE	1
LT	1464+91.00	W14-3-646448	NO PASSING ZONE	1
LT	1468+00.00	M-I100-2424 WITH SUPP M3-3-2412	ROUTE SIGN W/ SUPP DIR PLAQUE	2
LT	1469+26.00	W1-7-4824	TWO DIRECTION LARGE ARROW	1
RT	1470+80.00	M-I100-2424 WITH SUPP M3-3-2412	ROUTE SIGN W/ SUPP DIR PLAQUE	2
SILVER GLEN ROAD				
LT	200+30.00	R1-1-3636	STOP	1
TOTAL				10

FILE NAME = D:\60N13-sht-schedule.dgn
 MODEL = Default
 PLOT DRIVER = VBI_PDF_L1x17.plt



USER NAME = mmann
 DESIGNED - MCV
 DRAWN - CMM
 PLOT SCALE = 100.0000' / 1" = 100000000
 CHECKED - MTM
 PLOT DATE = 10/24/2012
 DATE - 10/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 SCALE: N.T.S. SHEET NO. 3 OF 3 SHEETS STA. TO STA.

F.A.P.
 RTE. 326 SECTION 106X-B COUNTY KANE TOTAL SHEETS 87 SHEET NO. 9
 CONTRACT NO. 60N13
 ILLINOIS FED. AID PROJECT