

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		85% FEDERAL 15% STATE 0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	17	17				
25200110	SODDING, SALT TOLERANT	SO YD	17	17				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	9	9				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20				
40600300	AGGREGATE (PRIME COAT)	TON	100	100				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	38	38				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	965	965				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	299	299				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2162	2162				
42001300	PROTECTIVE COAT	SO YD	53	53				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	9	9				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	24952	24952				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	17	17				
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	172	172				
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	107	107				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		85% FEDERAL 15% STATE 0005				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	149	149				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1				
60406000	FRAMES AND LIDS, TYPE I, OPEN LID	EACH	1	1				
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	2	2				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3645	3645				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	110	110				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20763	20763				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	418	418				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	160	160				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12" * SPECIALTY ITEMS	FOOT	162	162				

FILE NAME *	USER NAME * <i>ajp/161</i>	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE. 1598	SECTION 2010-159-R5	COUNTY COOK	TOTAL SHEETS 23	SHEET NO. 3		
<i>c:\work\p1598\p1598\2010159R5\1598\1598.dwg</i>	PLOT SCALE * 100.0000 / 1/4"	DRAWN -	REVISED -			SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE * 10/22/2002	CHECKED -	REVISED -						CONTRACT NO. 60N73			
		DATE -	REVISED -									