

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	85% FEDERAL 15% STATE 0005						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	85% FEDERAL 15% STATE 0005					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	42	42						Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51	51					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	7586	7586						Z0064800	SELECTIVE CLEARING	UNIT	106	106					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	110	110															
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20763	20763															
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	418	418															
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	160	160															
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	162	162															
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	42	42															
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	165	165															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	165	165															
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	245	245															
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	73	73															
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	100	100															
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	4	4															
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200															
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4															

△ 100% STATE  
\* SPECIALTY ITEMS

△

△