

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

80% FED.
15% STATE
5% VILLAGE

80% FED.
10% STATE
10% VILLAGE

80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						100% VILLAGE
				ROADWAY 0003 URBAN	RET. WALL 0040 URBAN	LIGHTING 0021 URBAN	TS-ZEMKE 0021 URBAN	TS-HIGGINS 0021 URBAN	TS-PATTON 0021 URBAN	
• 81702220	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C 350MCM	FOOT	120			120				
• 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	19,624			19,624				
• 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4			4				
• 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	184			184				
• 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	28			28				
• 83002200	LIGHT POLE, ALUMINUM, 40 FT. M.H., 6 FT. DAVIT ARM	EACH	6			6				
• 83050825	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. DAVIT ARM	EACH	47			47				
• 83050915	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-6 FT. DAVIT ARMS	EACH	20			20				
• 83057295	LIGHT POLE, WOOD, 50 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	106			106				
• 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	560			560				
* 83600352	LIGHT POLE FOUNDATION, METAL, 1 1/2" BOLT CIRCLE, 8 5/8" X 6'	EACH	4			4				
• 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	56			56				
• 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	111			111				
• 84200500	REMOVAL LIGHTING UNIT, SALVAGE	EACH	84			84				
• 84200804	REMOVAL OF POLE FOUNDATION	EACH	84			84				

14 • SPECIALITY ITEM

Rev-1-3-13

S00-16



USER NAME = lsupencheck	DESIGNED	REVISED
PLOT SCALE = 1/4"	DRAWN MMK	REVISED
PLOT DATE = 01-NOV-2012	CHECKED LLS	REVISED
	DATE 10/19/12	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 0105-WRS	COUNTY COOK	TOTAL SHEETS 537	SHEET NO. 21
CONTRACT NO. 60P35				
ILLINOIS FED. AID PROJECT				