

105EL01 105EL03 105EL04 105EL02 07/02

80% FED./20% STATE 80% FED. 15% STATE 5% VILLAGE 80% FED. 10% STATE 10% VILLAGE 80% FED. 20% STATE

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						100% VILLAGE WATERMAIN 0003 URBAN	
				ROADWAY 0003 URBAN	RET. WALL 0040 URBAN	LIGHTING 0021 URBAN	TS-ZEMKE 0021 URBAN	TS-HIGGINS 0021 URBAN	TS-PATTON 0021 URBAN		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	350	350							
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	155	155							
20101100	TREE TRUNK PROTECTION	EACH	25	25							
20200100	EARTH EXCAVATION	CU YD	62,227	62,227							
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	11,453	11,403							50
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1,330	1,330							
20800150	TRENCH BACKFILL	CU YD	6,510	6,248							262
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	120,576	120,576							
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	9,523	9,523							
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	55,292	55,292							
* 21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	514	514							
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	1,085	1,085							
* 21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	514	514							
* 25000210	SEEDING, CLASS 2A	ACRE	10.2	10.2							

\* SPECIALITY ITEM

S00-01



USER NAME: mkostr	DESIGNED	REVISED
DRAWN: MMK	CHECKED: LLS	REVISED
DATE: 10/19/12		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 0105-WRS	COUNTY COOK	TOTAL SHEETS 537	SHEET NO. 6
CONTRACT NO. 60P35				