

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						100% VILLAGE
				80% FED. / 20% STATE		80% FED. 15% STATE 5% VILLAGE	80% FED. 10% STATE 10% VILLAGE	80% FED. 20% STATE	WATERMAIN	
				ROADWAY 0003 URBAN	RET. WALL 0040 URBAN	LIGHTING 0021 URBAN	TS-ZEMKE 0021 URBAN	TS-HIGGINS 0021 URBAN		
28200200	FILTER FABRIC	SQ YD	432	432						
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	3,957	3,957						
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	120,235	120,235						
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	119,506	119,506						
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	63	63						
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,010	1,010						
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	27	27						
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	636	636						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	274	274						
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	495	495						
42000516	PORTLAND CEMENT CONCRETE PAVEMENT 10 3/4" (JOINTED)	SQ YD	88,748	88,748						
42001300	PROTECTIVE COAT	SQ YD	112,846	112,846						
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	762	762						

* SPECIALITY ITEM

S00-03



USER NAME = leupancheck	DESIGNED	REVISED -
PLOT SCALE = 1:1	DRAWN MMK	REVISED -
PLOT DATE = 27-OCT-2012	CHECKED LLS	REVISED -
	DATE 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 0105-WRS	COUNTY COOK	TOTAL SHEETS 537	SHEET NO. 8
CONTRACT NO. 60P35			ILLINOIS FED. AID PROJECT	