

80% FED / 20% STATE

80% FED.
15% STATE
5% VILLAGE

80% FED.
10% STATE
10% VILLAGE

80% FED.
20% STATE

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						100% VILLAGE
				ROADWAY 0003 URBAN	RET. WALL 0040 URBAN	LIGHTING 0021 URBAN	TS-ZEMKE 0021 URBAN	TS-HIGGINS 0021 URBAN	TS-PATTON 0021 URBAN	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	19,189	19,189						
42400800	DETECTABLE WARNINGS	SQ FT	120	120						
44000100	PAVEMENT REMOVAL	SQ YD	102,530	102,530						
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	5,360	5,360						
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	791	791						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9,828	9,828						
44000600	SIDEWALK REMOVAL	SQ FT	17,233	17,233						
44004000	PAVED DITCH REMOVAL	FOOT	461	461						
44004250	PAVED SHOULDER REMOVAL	SQ YD	20,394	20,394						
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,316	1,316						
48101500	AGGREGATE SHOULDERS, TYPE B, 6"	SQ YD	1,596	1,596						
48203040	HOT-MIX ASPHALT SHOULDERS, 10 3/4"	SQ YD	3,742	3,742						
48300515	PORTLAND CEMENT CONCRETE SHOULDERS 10 3/4"	SQ YD	19,996	19,996						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1						

* SPECIALITY ITEM

S00-04



USER NAME: rnkost	DESIGNED	REVISED
DRAWN: MMK	CHECKED: LLS	REVISED
DATE: 10/19/12		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE. 330	SECTION 0105-WRS	COUNTY COOK	TOTAL SHEETS 537	SHEET NO. 9
CONTRACT NO. 60P35			ILLINOIS FED. AID PROJECT	

SCALE: SHEET NO. OF SHEETS STA. TO STA.