

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

80% FED. 15% STATE 5% VILLAGE
 80% FED. 10% STATE 10% VILLAGE
 80% FED. 20% STATE

CONSTRUCTION CODE

100% VILLAGE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				ROADWAY 0003 URBAN	RET. WALL 0040 URBAN	LIGHTING 0021 URBAN	TS-ZEMKE 0021 URBAN	TS-HIGGINS 0021 URBAN	TS-PATTON 0021 URBAN	WATERMAIN 0003 URBAN	
50200100	STRUCTURE EXCAVATION	CU YD	708		708						
50300225	CONCRETE STRUCTURES	CU YD	298	18.1	280.0						
50300285	FORM LINER TEXTURED SURFACE	SQ FT	6,697		6,697						
50500505	STUD SHEAR CONNECTORS	EACH	1,286	184	1,102						
50800105	REINFORCEMENT BARS	POUND	60,530	60,530							
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	40,380	6,080	34,300						
50800515	BAR SPLICERS	EACH	94	94							
51500100	NAME PLATES	EACH	2		2						
54003000	CONCRETE BOX CULVERTS	CU YD	305	305							
542JC072	PIPE CULVERTS, CLASS C 72" (JACKED)	FOOT	66	66							
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1							
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3							
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1							
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1							

* SPECIALITY ITEM

S00-05



USER NAME: jupencheck	DESIGNED	REVISED -
	DRAWN: MMK	REVISED -
PLOT SCALE: 1/1	CHECKED: LLS	REVISED -
PLOT DATE: 01-NOV-2012	DATE: 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 0105-WRS	COUNTY COOK	TOTAL SHEETS 537	SHEET NO. 10
CONTRACT NO. 60P35			ILLINOIS FED. AID PROJECT	