

SUMMARY OF QUANTITIES

80% FED / 20% STATE

80% FED.

80% FED.

80% FED.

15% STATE

10% STATE

20% STATE

5% VILLAGE

10% VILLAGE

20% STATE

100%

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						WATERMAIN
				ROADWAY 0003 URBAN	RET. WALL 0040 URBAN	LIGHTING 0021 URBAN	TS-ZEMKE 0021 URBAN	TS-HIGGINS 0021 URBAN	TS-PATTON 0021 URBAN	
55100700	STORM SEWER REMOVAL 15"	FOOT	2,556	2,556						
55100900	STORM SEWER REMOVAL 18"	FOOT	296	296						
55101200	STORM SEWER REMOVAL 24"	FOOT	645	645						
56103000	DUCTILE IRON WATER MAIN, 6"	FOOT	124	76						48
56103300	DUCTILE IRON WATER MAIN, 12"	FOOT	1,019	815						204
56105200	WATER VALVE 12"	EACH	2	1						1
56400500	FIRE HYDRANT TO BE REMOVED	EACH	3	2						1
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	3	2						1
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	523		523					
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	7	7						
60107600	PIPE UNDERDRAINS 4"	FOOT	840		840					
60107700	PIPE UNDERDRAINS 6"	FOOT	2,189	2,189						
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	205	205						
60200105	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1						

\* SPECIALITY ITEM

S00-07



USER NAME = isupen@hntb.com	DESIGNED	REVISED -
	DRAWN MMK	REVISED -
PLOT SCALE = 1:1	CHECKED LLS	REVISED -
PLOT DATE = 01-NOV-2012	DATE 10/19/12	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 0105-WRS	COUNTY COOK	TOTAL SHEETS 537	SHEET NO. 12
CONTRACT NO. 60P35			ILLINOIS FED. AID PROJECT	