



8% MAX. ROLLOVER BETWEEN TRAVEL LANE AND SHOULDER

- PROPOSED LEGEND:**
- ① PORTLAND CEMENT CONCRETE PAVEMENT 10 3/4" JOINTED
  - ② STABILIZED SUBBASE (HMA), 4 1/2"
  - ③ AGGREGATE SUBGRADE IMPROVEMENT 12"
  - ④ COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24
  - ⑤ CONCRETE MEDIAN SURFACE, 4 INCH
  - ⑥ COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12
  - ⑦ CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT
  - ⑧ TOPSOIL FURNISH AND PLACE, 6"
  - ⑨ CONCRETE BARRIER, SINGLE FACE, 32 INCH HEIGHT
  - ⑩ LONGITUDINAL SAWED JOINT WITH NO. 6 TIE BARS @ 30" CTS
  - ⑪ LONGITUDINAL CONSTRUCTION JOINT WITH NO. 6 TIE BARS @ 24" CTS
  - ⑫ AGGREGATE SHOULDERS, TYPE B 6"
  - ⑬ CONCRETE BARRIER BASE
  - ⑭ CONCRETE MEDIAN, TYPE SB 6.12
  - ⑮ COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24
  - ⑯ PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH
  - ⑰ SEEDING (SEE LANDSCAPE PLANS)
  - ⑱ NO. 6 TIE BARS @ 24" CTS
  - ⑲ POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)
  - ⑳ POLYMERIZED HMA SURFACE, MIX "F", N90, 1-3/4"
  - ㉑ POLYMERIZED HMA BINDER, IL-19.0, N90, 2-1/4"
  - ㉒ CONCRETE MEDIAN, TYPE SM (SPECIAL)
  - ㉓ PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"
  - ㉔ CONCRETE MEDIAN, TYPE SB (SPECIAL)
  - ㉕ NOT USED
  - ㉖ STRIP REFLECTIVE CRACK CONTROL TREATMENT
  - ㉗ TEMPORARY PAVEMENT (FLEXIBLE DESIGN)
  - ㉘ HMA SURFACE COURSE, MIX "D", N70 1 1/2"
  - ㉙ 4" PVC (SURVEILLIANCE)
  - ㉚ AGGREGATE FILL
  - ㉛ SAND FILL
  - ㉜ CORRUGATED MEDIAN
  - ㉝ PORTLAND CEMENT CONCRETE SHOULDERS 10 3/4"
  - ㉞ GEOTECHNICAL FABRIC FOR GROUND STABILIZATION

\D:\60P35-TYPICAL.DGN, \D:\60P35-BORDER.DGN, \D:\60P35-TYPICAL-LEGEND.DGN, \D:\60P35-TYPICAL-SHT-TYPICAL.DGN, \D:\60P35-TYPICAL-LEGEND.DGN, \D:\60P35-TYPICAL-SHT-TYPICAL.DGN, \D:\60P35-TYPICAL-LEGEND.DGN, \D:\60P35-TYPICAL-SHT-TYPICAL.DGN

FILE NAME =	USER NAME = *USER*	DESIGNED - RJS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>				<b>PROPOSED MANNHEIM ROAD TYPICAL SECTIONS</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILEL#		DRAWN - HDU	REVISED -									SCALE: 1"=10'	SHEET NO.	OF SHEETS	STA. 119+38.52 TO STA. 143+86.76	ILLINOIS
TENG	TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	CHECKED - MCD	REVISED -									0105-WRS	COOK	537	36	
		DATE - 10/19/12	REVISED -									CONTRACT NO. 60P35				

TYP-05