

EARTHWORK SCHEDULE - RAMP NBWB									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
606+21.91	606+60.72	3	0	2	78	-76	0	23	20
606+60.72	606+89.43	4	0	3	41	-38	0	15	13
606+89.43	607+00.00	2	0	2	10	-9	0	5	6
607+00.00	607+25.00	15	0	11	15	-4	0	11	13
607+25.00	607+50.00	29	0	22	7	15	0	8	10
607+50.00	607+75.00	40	0	30	2	28	0	6	7
607+75.00	608+00.00	49	0	37	1	36	0	3	5
SUB-TOTAL		142	0	107	154	-48	0	71	74

EARTHWORK SCHEDULE - RAMP SBWB									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
802+68.39	803+17.44	63	0	47	2	45	0	6	12
803+17.44	803+65.60	86	0	65	5	60	0	9	13
803+65.60	804+14.25	108	0	81	4	77	0	8	10
804+14.25	804+62.10	114	0	86	0	86	0	5	6
804+62.10	805+09.76	107	0	80	0	80	0	4	5
805+09.76	805+55.30	98	0	74	0	74	0	4	5
805+55.30	805+64.22	18	0	14	0	14	0	1	1
SUB-TOTAL		594	0	446	11	435	0	37	52

EARTHWORK SCHEDULE - RAMP WBNB									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
702+00.00	702+25.00	37	0	28	0	28	0	3	1
702+25.00	702+60.11	42	0	32	1	31	0	6	3
702+60.11	702+90.00	28	0	21	4	17	0	7	5
702+90.00	703+07.96	13	0	10	5	5	0	5	4
703+07.96	703+30.00	12	0	9	6	3	0	6	5
703+30.00	703+56.15	12	0	9	7	2	0	6	5
SUB-TOTAL		144	0	108	23	85	0	33	23

EARTHWORK SCHEDULE - RAMP WBSB									
BEGIN STATION	END STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	AGGREGATE SUBGRADE IMPROVEMENT	TOPSOIL	TOPSOIL EXCAVATION AND PLACEMENT
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
509+50.00	509+75.00	49	0	37	1	36	0	3	3
509+75.00	510+00.00	45	0	34	1	33	0	4	4
510+00.00	510+42.24	66	0	50	4	46	0	8	7
510+42.24	510+80.46	44	0	33	6	27	0	9	8
510+80.46	511+26.99	40	0	30	12	18	0	13	12
SUB-TOTAL		244	0	183	24	159	0	37	34

* SHRINKAGE FACTOR 25%

SC-06



USER NAME = micosir	DESIGNED	REVISED -
	DRAWN MMK	REVISED -
PLOT SCALE = 1:1	CHECKED LLS	REVISED -
PLOT DATE = 24-OCT-2012	DATE 10/19/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105-WRS	COOK	537	49
CONTRACT NO. 60P35				
ILLINOIS FED. AID PROJECT				