

CONTRACT 60P35
SIGNING SCHEDULE

SIGN NO.	STATION	LEGEND / DESCRIPTION	MUTCD	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL - TYPE A	REMOVE SIGN PANEL - TYPE B	REMOVE SIGN PANEL - TYPE 1	REMOVE SIGN PANEL - TYPE 2	REMOVE SIGN PANEL - TYPE 3	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 3	RELOCATE SIGN PANEL - TYPE 1	RELOCATE SIGN PANEL - TYPE 2	RELOCATE SIGN PANEL - TYPE 3	METAL POST - TYPE A	METAL POST - TYPE B	WOOD SIGN POST
				WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	(EACH)	(EACH)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)
WB-HG-MP-846	493+45.00	Keep Right (Median)	R4-7	2.0	2.5	2.0	2.5			5.0			5.0						10		
WB-HG-MP-847	494+00.00	Keep Right (Median)	R4-7	2.0	2.5	2.0	2.5			5.0			5.0						10		
WB-HG-MP-848	494+00.00	left turn Only (arrow)	R3-5L	2.0	2.5	2.0	2.5			5.0			5.0						12		
WB-HG-MP-849	494+20.00	Chevron Left	W1-8L	2.0	2.5	2.0	2.5			5.0			5.0						12		
EB-HG-LP-850	494+93.00	Right turn Only (arrow)	R3-5R	2.0	2.5	2.5	3.0			5.0			7.5						12		
WB-HG-MP-851	494+93.00	Chevron Left	W1-8L	2.0	2.5	2.0	2.5			5.0			5.0						12		
WB-HG-MP-852	495+35.00	Chevron Left	W1-8L	2.0	2.5	2.0	2.5			5.0			5.0						12		
EB-HG-LP-853	496+73.00	Right turn Only (arrow)	R3-5R	2.5	2.5	2.5	3.0			6.3			7.5								
WB-HG-MP-854	496+95.00	Right Lane Ends	W4-2R	3.0	3.0	3.0	3.0				9.0			9.0					12		
EB-HG-MP-855	497+90.00	Red Light Photo Enforced	R10-19-DE	3.0	3.0	3.0	3.0	1.0			9.0			9.0					12		
WB-HG-LP-856	498+53.00	Cardinal Direction - West (Route)	M3-4	2.0	1.0	2.0	1.0			2.0			2.0								
WB-HG-LP-857	498+53.00	Illinois 72	M1-5	2.0	2.0	2.0	2.0	1.0		4.0			4.0							20	
EB-HG-LP-858	498+53.00	U.S. Route Sign 45	M1-4	2.0	2.0	2.0	2.0			4.0			4.0								
EB-HG-LP-859	498+53.00	U.S. Route Sign 12	M1-4	2.0	2.0	2.0	2.0			4.0			4.0								
EB-HG-LP-860	498+53.00	Directional Arrow (Both Ways)	M6-4	1.3	1.8	1.3	1.8			2.2			2.2								
WB-HG-EX-861	499+00.00	ARFF Staging Area "B" Right Arrow	D9-18a	6.0	4.0							24.0	0.0					24.0			24
EB-HG-EX-862	499+00.00	ARFF Staging Area "B" Right Arrow	D9-18a	6.0	4.0							24.0	0.0					24.0			24
WB-HG-LP-863	501+12.00	U.S. Route Sign 45	M1-4	2.0	2.0	2.0	2.0			4.0			4.0								
WB-HG-LP-864	501+12.00	U.S. Route Sign 12	M1-4	2.0	2.0	2.0	2.0			4.0			4.0								
WB-HG-LP-865	501+12.00	Directional Arrow (Both Ways)	M6-4	1.8	1.3	1.8	1.3			2.2			2.2								
WB-HG-MP-866	501+20.00	Pace Bus Stop		1.5	1.5	1.5	1.5			2.3			2.3								
EB-HG-LP-867	502+63.00	Cardinal Direction - East (Route)	M3-2	2.0	1.0	2.0	1.0			2.0			2.0								
EB-HG-LP-868	502+63.00	Illinois 72	M1-5	2.0	2.0	2.0	2.0			4.0			4.0								
EB-HG-LP-869	504+35.00	Speed Limit 40	R2-1	2.5	3.0	2.5	3.0			7.5			7.5								
WB-HG-MP-870	507+40.00	Junction	M2-1	2.0	1.0	2.0	1.0			2.0			2.0								
WB-HG-MP-871	507+40.00	U.S. Route Sign 45	M1-4	2.0	2.0	2.0	2.0			4.0			4.0								
WB-HG-MP-872	507+40.00	U.S. Route Sign 12	M1-4	2.0	2.0	2.0	2.0			4.0			4.0							20	
WB-HG-MP-873	507+40.00	Advanced street name (Mannheim Rd)	W16-8P	1.3	1.8	1.3	1.8			2.2			2.2						12		
EB-HG-LP-874	507+45.00	Watch for Water/Ice on Road		3.0	3.0	3.0	3.0		1.0		9.0			9.0					12		
WB-HG-MP-875	696+10.00	Keep Right (Median)	R4-7	2.0	2.5	2.0	2.5			5.0			5.0								
NB-MAN-MP-876	151+30.00	Movement Prohibition (No U Turn)	R3-4			2.0	2.0						4.0						6		
NB-MAN-MP-877	151+30.00	EXCEPT AUTHORIZED VEHICLES	R3-1I01			3.0	2.0						6.0								
SB-MAN-MP-878	151+30.00	Movement Prohibition (No U Turn)	R3-4			3.0	3.0							9.0							
SB-MAN-MP-879	151+30.00	EXCEPT AUTHORIZED VEHICLES	R3-1I01			3.0	2.0						6.0								
EB-HG-MP-880	498+99.00	left turn Only (arrow)	R3-5L			2.5	3.0						7.5						8		
EB-HG-MP-881	498+99.00	Keep Right (Median)	R4-7			2.0	2.5						5.0								
WB-HG-MP-882	501+20.00	left turn Only (arrow)	R3-5L			2.5	3.0						7.5						8		
WB-HG-MP-883	501+20.00	Keep Right (Median)	R4-7			2.0	2.5						5.0								
SB-MAN-LP-884	177+15.00	Right turn arrow	R3-5R			2.5	3.0						7.5						12		
SB-MAN-LP-885	181+23.00	Right lane must turn right	R3-7			2.5	3.0						7.5						12		
SB-MAN-MP-886	121+67.00	Added Lane	W4-3			3.0	3.0							9.0					12		
Totals								9.0	5.0	528.9	190.0	1576.0	481.8	289.0	1175.3	15.0	0.0	366.0	444	120	120.0



USER NAME = stephen.schuh
DESIGNED
DRAWN
PLOT SCALE = 10.0000" / 1"
PLOT DATE = 10/19/2012

DESIGNED
DRAWN
CHECKED
DATE 10/19/12

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGN SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105-WRS	COOK	537	213
CONTRACT NO. 60P35				
ILLINOIS FED. AID PROJECT				