

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS																100% G L E N V I E W
				ROADWAY	BRIDGE N. BRANCH CHICAGO RIVER	BRIDGE OVER I-94 EDENS EXPY	WILLOW RD AT IL ROUTE 43	WILLOW RD AT THREE LAKES DRIVE	WILLOW RD AT SUNSET RIDGE ROAD	WILLOW RD AT WAGNER RD	WILLOW RD AT PED ONLY CROSSING	WILLOW RD AT OLD WILLOW / NORTHFIELD RD	WILLOW RD AT CENTRAL AV / HAPP ROAD	IL ROUTE 43 AT THREE LAKES DRIVE	INTERCONNECT					
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% NORTHFIELD	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 15% STATE 5% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 20% NFIELD	80% FED 20% NFIELD ITEP	80% FED 20% STATE 20% NFIELD	80% FED 20% STATE 20% NFIELD ITEP	80% FED 20% STATE	
0003	0010	0014	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0003			
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	98607	98607																
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	216	216																
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	549	549																
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	689	689																
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	290	290																
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24																
40600895	CONSTRUCTING TEST STRIP	EACH	1	1																
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1924	1924																
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	162	162																
40803335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	293	293																
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	36	36																
40603585	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	429	429																
40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SQ YD	332	332																
40701966	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 1/4"	SQ YD	2965	2965																
42000426	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/4" (JOINTED)	SQ YD	55304	55304																
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	14074	14074																
42001300	PROTECTIVE COAT	SQ YD	31265	31265																
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	970	970																
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	43	43																
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	125	125																
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	80582	80582																
42400800	DETECTABLE WARNINGS	SQ FT	1522	1522																
44000100	PAVEMENT REMOVAL	SQ YD	72221	72221																
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	184	184																
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	204	204																
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2091	2091																
44000300	CURB REMOVAL	FOOT	310	310																
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	16752	16752																
44000600	SIDEWALK REMOVAL	SQ FT	46932	46932																
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	218	218																
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	262	262																
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SQ YD	345	345																
44003100	MEDIAN REMOVAL	SQ FT	7186	7186																

- * DENOTES SPECIALTY ITEM
- \$ 80% FEDERAL, 20% NORTHFIELD (ITEP)
- + 90% STATE, 10% NORTHFIELD
- & 40% STATE, 60% NORTHFIELD
- # 100% NORTHFIELD
- NP NON-PARTICIPATING ITEM

Rev 1-7-13