

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE
				ROADWAY 0003 URBAN
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	698	698
25100115	MULCH, METHOD 2	ACRE	8	8
25100630	EROSION CONTROL BLANKET	SQ YD	36992	36992
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	25	25
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1700	1700
28000305	TEMPORARY DITCH CHECKS	FOOT	2040	2040
28000400	PERIMETER EROSION CONTROL BARRIER	FOOT	9425	9425
28000510	INLET FILTERS	EACH	4	4
28001000	AGGREGATE EROSION CONTROL	TON	13	13
28100107	STONE RIPRAP, CLASS A4	SQ YD	123	123
28200200	FILTER FABRIC	SQ YD	123	123
30300108	AGGREGATE SUBGRADE IMPROVEMENT 8"	SQ YD	3437	3437
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	46538	46538
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	4257	4257
31102000	SUBBASE GRANULAR MATERIAL, TYPE C	CU YD	852	852

• SPECIALTY ITEM

TYLIN INTERNATIONAL

DESIGNED	JTP	REVISED	
DRAWN	JTP	REVISED	
CHECKED	JPM	REVISED	
DATE	9/19/2012	REVISED	11/2/2012

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STUENKEL ROAD AT I-57 (HARLEM AVENUE TO RIDGELAND AVENUE)
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 2 OF 9 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2012-048R	WILL	206	5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60V41	