

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE
				ROADWAY 0003 URBAN
78300100	PAVEMENT MARKING REMOVAL	SO FT	928	928
X0325318	LIGHTWEIGHT CELLULAR CONCRETE FILL	CU YD	3310	3310
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	12	12
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3
X4023000	TEMPORARY ACCESS (ROAD)	EACH	6	6
X6640300	CHAIN LINK FENCE REMOVAL	FOOT	265	265
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	6	6
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
Z0002750	BARRICADE-TYPE III	EACH	2	2
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0016702	DETOUR SIGNING	L SUM	1	1
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	208	208
Z0037000	PAVEMENT CRACKING AND SEATING	SO YD	958	958
Z0062456	TEMPORARY PAVEMENT	SO YD	605	605

• SPECIALTY ITEM

**TYLIN INTERNATIONAL**

USER NAME *	DESIGNED - JTP	REVISED
	DRAWN - JTP	REVISED
PLOT SCALE *	CHECKED - JPM	REVISED
PLOT DATE	DATE - 9/19/2012	REVISED - 11/2/2012

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**STUENKEL ROAD AT I-57 (HARLEM AVENUE TO RIDGELAND AVENUE)**

**SUMMARY OF QUANTITIES**

SCALE: N.T.S. SHEET 9 OF 9 SHEETS STA. TO STA.

P.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2012-04BR	WILL	206	12
CONTRACT NO. 60V41			ILLINOIS FED. AID PROJECT	