150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

765
760
755

PROPOSED ℄
STUENKEL RD.

PROPOSED R.O.W.
EXISTING R.O.W.
EXISTING R.O.W.
PROPOSED R.O.W.

1:3 1:4 1:4 1:3

757.91
755.14
755.67

STA. 15952+50.00

QUANTITIES (SF)
EXCAVATION = 41.3
UNSUITABLE = 130.6
EMBANKMENT = 59.3

PROPOSED ℄
STUENKEL RD.

PROPOSED R.O.W.
EXISTING R.O.W.
EXISTING R.O.W.
PROPOSED R.O.W.

1:3 1:4 1:4 1:3

757.41
754.50
754.97

STA. 15952+00.00

QUANTITIES (SF)
EXCAVATION = 40.0
UNSUITABLE = 170.5
EMBANKMENT = 69.7

PROPOSED ℄
STUENKEL RD.

PROPOSED R.O.W.
EXISTING R.O.W.
EXISTING R.O.W.
PROPOSED R.O.W.

1:3 1:3 1:3 1:3

757.16
753.86
754.28

STA. 15951+50.00

ADDITIONAL REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (TYP)

QUANTITIES (SF)
EXCAVATION = 39.6
UNSUITABLE = 165.6
EMBANKMENT = 80.8

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
NOTE BOOK		
AREAS		
NO.	AREAS CHECKED	

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
NOTE BOOK		
AREAS		
NO.	AREAS CHECKED	

TYLIN INTERNATIONAL

USER NAME =	DESIGNED - JDF	REVISED -
	DRAWN - JDF	REVISED -
PLOT SCALE =	CHECKED - JPM	REVISED -
PLOT DATE =	DATE - 9/19/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STUENKEL ROAD AT I-57 (HARLEM AVE. TO RIDGELAND AVE.)
PROPOSED STUENKEL ROAD CROSS SECTIONS

SCALE: 1" = 10' H, 1" = 5' V | SHEET NO. OF SHEETS | STA. 15951+50.00 TO STA. 15952+50.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2012-048R	WILL	206	128
		CONTRACT NO. 60V41		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

P:\602612(I-57_@_Stuenkel)\Road\C_2(Interchange)\C2_Stuenkel_50XS_F_SHT.dgn