FINAL SURVEY		BY	DATE
	SURVEYED		
	PLOTTED		
	TEMPLATE		
NOTE BOOK	AREAS		
NO.	AREAS CHECKED		

PROPOSED ℄ STUENKEL RD.

PROPOSED R.O.W. | EXISTING R.O.W. | EXISTING R.O.W. | PROPOSED R.O.W.

763.44

1:3 | 1:4 | 1:4 | 1:3

758.97 | 760.01

AT&T DUCT

QUANTITIES (SF)
EXCAVATION = 26.2
UNSUITABLE = 115.9
EMBANKMENT = 102.3

STA. 15965+50.00

PROPOSED ℄ STUENKEL RD.

762.76

758.34 | 759.32

AT&T DUCT

QUANTITIES (SF)
EXCAVATION = 28.2
UNSUITABLE = 117.3
EMBANKMENT = 100.4

STA. 15965+00.00

PROPOSED ℄ STUENKEL RD.

762.22

757.71 | 758.62

AT&T DUCT

QUANTITIES (SF)
EXCAVATION = 29.4
UNSUITABLE = 121.3
EMBANKMENT = 97.3

STA. 15964+50.00

ORIGINAL SURVEY		BY	DATE
	SURVEYED		
	PLOTTED		
	TEMPLATE		
NOTE BOOK	AREAS		
NO.	AREAS CHECKED		

TYLIN INTERNATIONAL

USER NAME =	DESIGNED - JDF	REVISED -	
	DRAWN - JDF	REVISED -	
PLOT SCALE =	CHECKED - JPM	REVISED -	
PLOT DATE =	DATE - 9/19/2012	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STUENKEL ROAD AT I-57 (HARLEM AVE. TO RIDGELAND AVE.)
PROPOSED STUENKEL ROAD CROSS SECTIONS

SCALE: 1" = 10' H, 1" = 5' V | SHEET NO. OF SHEETS | STA. 15964+50.00 TO STA. 15965+50.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2012-048R	WILL	206	139
		CONTRACT NO. 60V41		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

P:\602612(I-57_@_Stuenkel)\Road\C_2(Interchange)\C2_Stuenkel_50XS_F_SHT.dgn