

**INDEX OF SHEETS**

- 1. TITLE SHEET
- 2. INDEX OF SHEETS AND GENERAL NOTES
- 3. LOCATION MAP
- 4.-6. SUMMARY OF QUANTITIES
- 7.-12. DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS

**TRAFFIC SIGNAL PLANS**

PAGE	TS	INTERSECTION NAME
13.	12260	U.S. 6 AT I-55 EAST RAMPS
14.	12265	U.S. 6 AT I-55 WEST RAMPS
15.	12267	U.S. 6 (EAMES ST) AT BLUFF / NAVAJO ROAD
16.	2268	U.S. 6 (EAMES ST) AT ROBERTS AVENUE / STEVE RITTOF DRIVE
17.	12266	U.S. 6 (EAMES ST) AT TRYON STREET
18.	7414	U.S. 45 (LAGRANGE RD) AT OLD FRANKFORT WAY
19.	7413	U.S. 45 (LAGRANGE RD) AT NEBRASKA STREET
20.	21820	IL 53 (S. CHICAGO ST) AT I-80 WEST RAMP
21.	22191	U.S. 52 (JEFFERSON ST) AT I-55 EAST FRONTAGE ROAD
22.	22180	U.S. 52 (JEFFERSON ST) AT I-55 EAST RAMPS
23.	22185	U.S. 52 (JEFFERSON ST) AT I-55 WEST RAMPS
24.	7450	U.S. 30 AT WASHINGTON STREET
25.	7385	RICHARDS STREET AT I-80 NORTH RAMPS
26.	7390	RICHARDS STREET AT I-80 SOUTH RAMPS
27.	7460	U.S. 30 (CASS ST) AT BRIGGS STREET
28.	7510	IL 7 / IL 53 AT IL 7 / RENWICK ROAD
29.	7511	IL 7 (159TH ST) AT COUGAR ROAD
30.	11630	U.S. 45 (LAGRANGE RD) AT ST. FRANCIS ROAD
31.	7440	U.S. 30 (LINCOLN HWY) AT NELSON ROAD
32.	7585	IL 59 / U.S. 30 AT IL 126
33.	7560	IL 53 (INDEPENDENCE BLVD) AT AIRPORT ROAD
34.	7859	IL 53 (JOLIET RD) AT HONEYTREE DRIVE
35.	7866	IL 53 (JOLIET RD) AT ENTERPRISE DRIVE
36.	7575	IL 53 (JOLIET RD) AT NORMANTOWN / DEVONWOOD ROAD
37.	9105	IL 53 (INDEPENDENCE BLVD) AT ROMEO ROAD (135TH ST)
38.	7495	U.S. 52 (JEFFERSON ST) AT IL 59
39.	7496	U.S. 52 (JEFFERSON ST) AT BROOKSHORE DR
39A.	7497	U.S. 52 (JEFFERSON ST) AT RIVER RD

**GENERAL NOTES**

THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", JANUARY 1, 2012; MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, LATEST EDITION; PROJECT SPECIFICATIONS; ALL APPLICABLE REQUIREMENTS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION; THE CITIES OF JOLIET AND LOCKPORT; THE VILLAGE OF CHANNAHON, FRANKFORT, PLAINFIELD, AND ROMEOVILLE; THE WILL COUNTY DEPARTMENT OF HIGHWAYS; ALL APPLICABLE REQUIREMENTS OF THE ORDINANCES OF AUTHORITIES HAVING JURISDICTION; AND ALL ADDENDA THERETO SHALL GOVERN THIS WORK.

THE STANDARD SPECIFICATIONS, PROJECT SPECIFICATIONS, CONSTRUCTION PLANS, AND SUBSEQUENT DETAILS ARE ALL TO BE CONSIDERED AS PART OF THE CONTRACT. INCIDENTAL ITEMS OR ACCESSORIES NECESSARY TO COMPLETE THIS WORK MAY NOT BE SPECIFICALLY NOTED BUT ARE TO BE CONSIDERED A PART OF THE CONTRACT.

WHENEVER, DURING CONSTRUCTION OPERATIONS, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC. SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL WILL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR'S FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OF UNSTABLE MATERIALS CREATED AS A RESULT THEREOF.

THE CONTRACTOR SHALL SOLELY BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ADEQUATE SIGNS, TRAFFIC CONTROL DEVICES, AND WARNING DEVICES TO INFORM AND PROTECT THE PUBLIC DURING ALL PHASES OF CONSTRUCTION.

THE CONTRACTOR IS RESPONSIBLE FOR RETURNING ALL AREAS AFFECTED BY EQUIPMENT OR LABORERS TO EXISTING CONDITIONS. THE CONTRACTOR IS ALSO RESPONSIBLE FOR PROTECTING ALL NEW WORK UNTIL COMPLETION OF THIS CONTRACT.

EXISTING UTILITIES: WHEN THE PLANS OR SPECIAL PROVISIONS INCLUDE INFORMATION PERTAINING TO THE LOCATION OF UNDERGROUND UTILITY FACILITIES, SUCH INFORMATION IS BASED ON RECORD INFORMATION PROVIDED BY THE INDIVIDUAL UTILITY OWNERS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES. THE CONTRACTOR SHALL ALSO CONTACT JULIE, I.E. TO OBTAIN LOCATES OF THE RESPECTIVE UTILITY COMPANIES UNDERGROUND FACILITIES.

RESTORATION OF WORK AREA: RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC. AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD IN ACCORDANCE TO STANDARD SPECIFICATIONS ARTICLE 252 WHICH SHALL INCLUDE THE REQUIRED WATERING PER ARTICLE 252.08. ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDING IN ACCORDANCE WITH STANDARD SPECIFICATIONS ARTICLE 250 AND 251, RESPECTIVELY.

THE GENERAL CONTRACTOR IS REQUIRED TO HIRE AN ENVIRONMENTAL FIRM WITH AT LEAST FIVE (5) DOCUMENTED LEAKING UNDERGROUND STORAGE TANK CLEANUPS OR THAT IS PRE-QUALIFIED IN HAZARDOUS WASTE BY THE DEPARTMENT TO REMEDIATE THE SOIL CONTAMINATION AND MONITOR FOR WORKER PROTECTION.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION. THIS SHALL INCLUDE LOCATING THE MAST ARM FOUNDATIONS AND VERIFYING THE MAST ARM LENGTH.

THE EXACT LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE ORDERING ANY MATERIALS AND STARTING ANY WORK. FOR LOCATIONS OF UTILITIES, LOCALLY OWNED EQUIPMENT, LEASED ENFORCEMENT CAMERA SYSTEM FACILITIES, AND IDOT UNDERGROUND FACILITIES, CONTACT THE LOCAL COUNTIES, MUNICIPALITIES, AND IDOT FOR LOCATES. THE CONTRACTOR SHALL CALL 'JULIE' AT (800) 892-0123 OR 811, IN THE CITY OF CHICAGO CONTACT DIGGER AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED UTILITIES (48 HOURS NOTIFICATION REQUIRED).

THE CONTRACTOR SHALL CHECK THE PROPOSED TRAFFIC SIGNAL EQUIPMENT LOCATIONS FOR OVERHEAD UTILITY CONFLICTS. THE CONTRACTOR SHALL COORDINATE ANY CONFLICTS WITH THE UTILITY COMPANIES AND THE RESIDENT ENGINEER BEFORE ORDERING MATERIALS.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, LOCAL GOVERNMENT AGENCIES, AND IDOT.

THE CONTRACTOR SHALL RELOCATE ANY EXISTING SIGN PANELS FROM PAINTED POSTS THAT ARE INDICATED FOR REPLACEMENT TO A NEW POST AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. THE COST OF REMOVAL, RELOCATION, AND ANY NEW MOUNTING HARDWARE NECESSARY TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE PAY ITEM OF THE LENGTH AS SPECIFIED IN THE PLANS.

FILE NAME * S:\WP\Design\PB\60V74 Will County LED	USER NAME * blumbergo Installation\Final revisions CAD 11/3-12\60V74	DESIGNED - JRD DRAWN - ZCW	REVISED - PB 10/25/2012 REVISED - PB 11/08/2012	<p align="center"><b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b></p>	<p align="center"><b>INDEX OF SHEETS &amp; GENERAL NOTES</b></p>				F.A. RTE. VARIES	SECTION 2012-067 I	COUNTY WILL	TOTAL SHEETS 39	SHEET NO. 2
Default	PLOT SCALE * 48.300000 1 / in. PLOT DATE * 11/07/2012	CHECKED - KLB DATE - 10-12-12	REVISED - REVISED -						SCALE: NONE	SHEET	OF	SHEETS	STA.
<p align="right">GHA #4085.886</p>													
										<p align="center"><b>CONTRACT NO. 60V74</b></p>			