

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = windat	DESIGNED -	REVISED - R.	R. MIRS 09-15-97	·		ARTERIAL ROAD		F.A.P.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw_work\pwidot\windat\d0319376\DistS		DRAWN -	+	R. MIRS 12-11-97	STATE OF ILLINOIS	INFORMATION CION			607	2012-069RS	WILL	28	27
	PLOT SCALE = 100.0000 '/ in.	CHECKED -		AMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION					TC-22	CONTRACT	NO. 60)V75
	PLOT DATE = 10/26/2012	DATE -	REVISED - C.	C. JUCIUS 01-31-07					FED. ROAD	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			