

## INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS
3	NOTES FOR BRIDGE PAINTING
4	SUMMARY OF QUANTITIES
5-8	LOCATION MAPS
9-12	BRIDGE PAINTING PLANS LOC) 1 (SN 016-1015)
13-15	BRIDGE PAINTING PLANS LOC) 2 (SN 016-1099)
16-18	BRIDGE PAINTING PLANS LOC) 3 (SN 016-0573)
19-21	BRIDGE PAINTING PLANS LOC) 4 (SN 016-0919)
21-23	BRIDGE PAINTING PLANS LOC) 5 (SN 016-0322)
24	ENTRANCE AND EXIT RAMP CLOSURE DETAILS (TC-08)
25	SINGLE LANE WEAVE AND MULTI-LANE WEAVE (TC-09)
26	TRAFFIC CONTROL DETAILS FOR FREEWAYS SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)
27	ARTERIAL ROAD INFORMATION SIGN (TC-22)

## STATE STANDARDS

701101-03	OFF-RD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701400-06	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-07	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-08	MULTI-LANE, TRAFFIC CONTROL AT ENTRANCE OR EXIT RAMP
701422-05	LANE CLOSURE, MULTILANE, FOR SPEEDS $\geq$ 45 MPH TO 55 MPH
701426-05	MULTI-LANE, INTERMITTENT OR MOVING OPERATION
701446-04	TWO LANE CLOSURE FREEWAY/EXPRESSWAY
701501-06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701602-06	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
701606-08	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701801-05	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-03	TRAFFIC CONTROL DEVICES

## GENERAL NOTES

1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.
2. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, THE CITIES OF MARKHAM AND CHICAGO HEIGHTS; AND THE VILLAGES OF FLOSSMOOR, WORTH AND THORNTON.
3. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
5. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR FOR EXPRESSWAYS AT (847)705-4151 AND FOR ARTERIALS AT (847)705-4470, A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
6. THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE BRIDGE INSPECTORS.
7. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
8. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
9. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROTECT AND PRESERVE THE EXISTING BRIDGE LIGHTING AT ANY LOCATIONS THAT LIGHTING IS ENCOUNTERED ADJACENT TO AN AREA TO BE CLEANED AND PAINTED.
10. THE "ARTERIAL ROAD INFORMATION SIGN (TC-22)" IS APPLICABLE ONLY TO ARTERIAL ROADS AND SHALL NOT BE APPLIED TO EXPRESSWAYS.
11. THE CONTRACTOR SHALL NOT BE ALLOWED TO SET UP PERMANENT LANE CLOSURES FOR THIS CONTRACT. LANE CLOSURES SHALL ONLY BE PERMITTED WHILE THE CONTRACTOR IS WORKING.

*Rev. Sheet 1-3-13*

FILE NAME *	USER NAME * midyjo	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS, GENERAL NOTES &amp; STATE STANDARDS</b>	F.A.2 RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\p\work\pvidot\midyjo\0317439\018861	rahtsolen.dgn	DRAWN -	REVISED -			VAR.	2012-074BP	COOK	27	2	
*MODELNAME*	PLOT SCALE * 100.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 60V84					
	PLOT DATE * 12/4/2012	DATE -	REVISED -			ILLINOIS NON - FED. AID PROJECT					
						SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____					