

SP	SPECIALTY ITEM	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	RECON NO CAP 0004	SAFETY LIGHTING 0021	LCDOT MISC.
*		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	195	195		
*		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	273	273		
		20101000	TEMPORARY FENCE	FOOT	250	250		
*		20101100	TREE TRUNK PROTECTION	EACH	16	16		
		20101200	TREE ROOT PRUNING	EACH	20	20		
		20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	10	10		
		20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	10	10		
		20200100	EARTH EXCAVATION	CU YD	6,580	6,580		
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,100	2,100		
*		20800150	TRENCH BACKFILL	CU YD	1,417	1,417		
		21001000	GEO TECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	8,628	8,628		
+		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5832	5832		
*	+	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	182	182		
*	+	21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	62	62		
*		21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	200	200		
+		25000210	SEEDING, CLASS 2A	ACRE	1	1		
+		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	112	112		
+		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	112	112		
+		25100630	EROSION CONTROL BLANKET	SQ YD	4596	4596		
+		25200110	SODDING, SALT TOLERANT	SQ YD	2105	2105		
+		25200200	SUPPLEMENTAL WATERING	UNIT	13	13		
+		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	136	136		
*		28000305	TEMPORARY DITCH CHECKS	FOOT	42	42		
*		28000400	PERIMETER EROSION BARRIER	FOOT	463	463		
		28000510	INLET FILTERS	EACH	26	26		
		28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	33	33		
*		28200200	FILTER FABRIC	SQ YD	216	216		
*		30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	630	630		
*		30300112	AGGREGATE SUBGRADE IMPROVEMENT, 12"	SQ YD	9,471	9,471		
		35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1,798	1,798		
		40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	9	9		
*		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,600	1,600		
		40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	237	237		
		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	61	61		

SP	SPECIALTY ITEM	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	RECON NO CAP 0004	SAFETY LIGHTING 0021	LCDOT MISC.
		40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	7,192	7,192		
		42000564	PORTLAND CEMENT CONCRETE PAVEMENT 14" (JOINTED)	SQ YD	248	248		
		42001200	PAVEMENT FABRIC	SQ YD	248	248		
		42001300	PROTECTIVE COAT	SQ YD	2,049	2,049		
		42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	9,391	9,391		
*		42400800	DETECTABLE WARNINGS	SQ FT	319	319		
		44000100	PAVEMENT REMOVAL	SQ YD	5,910	5,910		
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	682	682		
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,497	1,497		
		44004250	PAVED SHOULDER REMOVAL	SQ YD	408	408		
		44200116	PAVEMENT PATCHING, TYPE I, 10 INCH	SQ YD	40	40		
		48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	516	516		
		48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	327	327		
		54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	55	55		
		54213447	END SECTIONS 12"	EACH	1	1		
		54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1		
		54215550	METAL END SECTIONS 15"	EACH	4	4		
		550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	480	480		
		550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	770	770		
		550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	150	150		
		55100200	STORM SEWER REMOVAL 6"	FOOT	80	80		
		55100500	STORM SEWER REMOVAL 12"	FOOT	664	664		
		55100700	STORM SEWER REMOVAL 15"	FOOT	31	31		
*	+	56100030	DUCTILE IRON WATER MAIN TEE, 10" X 6"	EACH	1	1		
*	+	56103800	DUCTILE IRON WATER MAIN, MECHANICAL JOINT 6"	FOOT	12	12		
*	+	56104000	DUCTILE IRON WATER MAIN, MECHANICAL JOINT 10"	FOOT	192	192		
*	+	56105100	WATER VALVES 10"	EACH	2	2		
*	+	56109422	DUCTILE IRON WATER MAIN FITTINGS 10" 45.00 DEGREE BEND	EACH	4	4		
*	+	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	1	1		
*	+	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1	1		
*		60100905	PIPE DRAINS 4"	FOOT	100	100		
*		60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
*		60200205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4		
		60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2		

FILE NAME: I:\LAWRENCE\1122401\Drawings\Cadd\Sheet\SDG.L.dwg



USER NAME = Jeff Sedig
 PLOT SCALE = 1/8" = 1'-0"
 PLOT DATE = 11/29/2012

DESIGNED - MNB
 DRAWN - MNB
 CHECKED - CMC
 DATE - 10/22/2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0192	06-00153-07-CH	LAKE	120	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 63682				