


FILE NAME = L:\L\MECO\122401\Draw\CADD\Sheet\S00\_2.dgn

SP	SPECIALTY ITEM	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	RECON NO CAP 0004	SAFETY LIGHTING 0021	LCDOT MISC.
		60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	14	14		
		60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1		
		60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	7	7		
		60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2	2		
*		60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
		60255500	MANHOLES TO BE ADJUSTED	EACH	4	4		
		60500040	REMOVING MANHOLES	EACH	3	3		
		60500050	REMOVING CATCH BASINS	EACH	8	8		
		60500060	REMOVING INLETS	EACH	1	1		
*		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	696.0	696.0		
*		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3,082.0	3,082.0		
*		60608552	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	283	283		
		60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1,602	1,602		
		60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	312	312		
	+	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	200	200		
*		63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
		63200310	GUARDRAIL REMOVAL	FOOT	330	330		
	+	66500105	WOVEN WIRE FENCE, 4'	FOOT	328	328		
		66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	10	10		
		67100100	MOBILIZATION	L SUM	1	1		
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	14	14		
		72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	230	230		
	+	78000100	THERMOPLASTIC PLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	149	149		
	+	78000200	THERMOPLASTIC PLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,440	5,440		
	+	78000300	THERMOPLASTIC PLASTIC PAVEMENT MARKING - LINE 5"	FOOT	3,243	3,243		
	+	78000500	THERMOPLASTIC PLASTIC PAVEMENT MARKING - LINE 8"	FOOT	691	691		
	+	78000600	THERMOPLASTIC PLASTIC PAVEMENT MARKING - LINE 12"	FOOT	616	616		
*		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	32	32		
	+	78200410	GUARDRAIL MARKERS, TYPE A	EACH	11	11		
*		80400100	ELECTRICAL SERVICE INSTALLATION	EACH	1		1	
*		80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1	
	+	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	50		50	
	+	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	761		761	
	+	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	32		32	
	+	81028720	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1" DIA.	FOOT	200	200		
	+	81400100	HANDHOLE	EACH	7		7	

SP	SPECIALTY ITEM	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	RECON NO CAP 0004	SAFETY LIGHTING 0021	LCDOT MISC.
	+	81603045	UNIT DUCT, 600V, 3-1/C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	3080		3080	
	+	81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	276		276	
	+	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	56		56	
	+	81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	168		168	
	+	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	18		18	
	+	82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480 VOLT, 100 AMP	EACH	1		1	
*	+	83060120	LIGHT POLE, GALVANIZED STEEL, 30 FT. M.H., 8 FT. MAST ARM	EACH	15		15	
*	+	83060150	LIGHT POLE, GALVANIZED STEEL, 30 FT. M.H., 15 FT. MAST ARM	EACH	3		3	
*	+	83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	234		234	
	+	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	18		18	
*	+	B2000668	TREE, AMELANCHIER X GRANDIFLORA (APPLE SERVICEBERRY), 7' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	3	3		
*	+	K0013000	PERENNIAL PLANTS, PRAIRIE TYPE, 2" DIAMETER BY 4" DEEP PLUG	UNIT	6	6		
*	+	K1003680	MULCH	SQ YD	40	40		
*		X0322936	REMOVE EXISTING FLARED END SECTION	EACH	5	5		
*	+	X0324597	CLOSED CIRCUIT TELEVISION CABINET	EACH	1	1		
*		X0325003	REMOVE EXISTING VALVE AND VAULT	EACH	1	1		
*	+	X0326463	WIRELESS VIDEO DISTRIBUTION SYSTEM	LSUM	1	1		
*	+	X0326812	CAT 5 ETHERNET CABLE	FOOT	50	50		
*		X2010510	CLEARING AND GRUBBING	LSUM	1	1		
*		X2510635	HEAVY DUTY EROSION CONTROL BLANKET, SPECIAL	SQ YD	122	122		
*		X2800400	PERIMETER EROSION BARRIER, SPECIAL	FOOT	989	989		
*		X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	6	6		
*	+	X5610710	WATER MAIN REMOVAL, 10"	FOOT	180	180		
*	+	X5630710	CONNECTION TO EXISTING WATER MAIN 10"	EACH	2	2		
*		X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	1,870	1,870		
*		X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	CAL MO	3	3		
*		X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1	1		
*		XX000856	MAILBOX REMOVAL AND RELOCATION	EACH	2	2		
*		XX001095	MAILBOX REMOVAL AND REPLACEMENT	EACH	1	1		
*	+	XX005940	REMOTE CONTROLLED VIDEO SYSTEM	EACH	1	1		



USER NAME - Jeff Sedig	DESIGNED - MNB	REVISED -
PLT SCALE - 40,000' / 1"	DRAWN - MNB	REVISED -
PLT DATE - 11/29/2012	CHECKED - CMC	REVISED -
	DATE - 10/22/2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	TO STA.	FROM STA.
	2 OF 3 SHEETS		

F.A.J. RIE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0192	06-00153-07-CH	LAKE	120	4
CONTRACT NO. 63682				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				