

ROADWAY SCHEDULE											
SHEET	LOCATION	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	AGGREGATE BASE COURSE, TYPE B-6"	AGGREGATE SUBGRADE IMPROVEMENT	AGGREGATE SUBGRADE IMPROVEMENT, 12"	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	CONCRETE MEDIAN SURFACE, 4 INCH	CONCRETE MEDIAN, TYPE SB-6.12	STAMPED COLORED PORTLAND CEMENT CONCRETE	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06
		STATION TO STATION	21001000	35101800	30300001	30300112	60603800	60605000	60618300	60619600	XX006898
		SQ YD	SQ YD	CU YD	SQ YD	FOOT	FOOT	SQ FT	SQ FT	SQ FT	FOOT
ROADWAY PLAN & PROFILE - SHEET 1 OF 5	STA. 101+57.24 TO STA. 103+50.00	675.9	37.5	-	773.5	0.0	345.7	-	-	0.0	0.0
ROADWAY PLAN & PROFILE - SHEET 2 OF 5	STA. 103+50.00 TO STA. 109+50.00	4053.2	974.9	415.0	4040.0	219.4	1328.3	-	-	2229.2	282.7
ROADWAY PLAN & PROFILE - SHEET 3 OF 5	STA. 109+50.00 TO STA. 112+20.00	962.6	46.1	-	1038.4	0.0	242.1	-	-	0.0	0.0
ROADWAY PLAN & PROFILE - SHEET 4 OF 5	STA. 65+66.79 TO STA. 70+00.00	792.5	401.3	-	862.6	0.0	231.7	-	-	0.0	0.0
ROADWAY PLAN & PROFILE - SHEET 5 OF 5	STA. 72+00.00 TO STA. 77+34.82	2142.9	337.9	-	2375.1	0.0	776.6	-	-	0.0	0.0
CONSTRUCTION DETAILS - SHEET 1 OF 5	SPLITTER ISLAND - WEST LEG	-	-	25.6	95.6	119.0	39.6	402.6	78.0	402.6	-
CONSTRUCTION DETAILS - SHEET 2 OF 5	SPLITTER ISLAND - EAST LEG	-	-	25.4	95.3	119.2	39.2	401.6	78.1	401.6	-
CONSTRUCTION DETAILS - SHEET 3 OF 5	SPLITTER ISLAND - SOUTH LEG	-	-	25.9	96.6	119.0	40.4	407.3	77.5	407.3	-
CONSTRUCTION DETAILS - SHEET 4 OF 5	SPLITTER ISLAND - NORTH LEG	-	-	24.7	93.6	118.9	38.3	389.7	78.1	389.7	-
TOTAL		8628	1798	517	9471	696	3082	1602	312	3832	283

ROADWAY SCHEDULE										
SHEET	LOCATION	TEMPORARY ACCESS (PRIVATE ENTRANCE)	AGGREGATE SHOULDERS, TYPE B-6"	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	DETECTABLE WARNINGS
		STATION TO STATION	X4021000	48101500	40600100	40600982	40603085	40603340	40701881	42400100
		EACH	SQ YD	GAL	SQ YD	TON	TON	SQ YD	SQ FT	SQ FT
ROADWAY PLAN & PROFILE - SHEET 1 OF 5	STA. 101+57.24 TO STA. 103+50.00	1.0	17.5	139.7	62.0	-	12.2	599.0	0.0	0.0
ROADWAY PLAN & PROFILE - SHEET 2 OF 5	STA. 103+50.00 TO STA. 109+50.00	1.0	0.0	641.7	0.0	-	9.9	3125.9	6514.1	118.9
ROADWAY PLAN & PROFILE - SHEET 3 OF 5	STA. 109+50.00 TO STA. 112+20.00	1.0	226.3	198.0	123.7	0.7	13.5	877.5	0.0	0.0
ROADWAY PLAN & PROFILE - SHEET 4 OF 5	STA. 65+66.79 TO STA. 70+00.00	0.0	75.1	214.4	50.5	71.5	5.7	703.2	749.7	0.0
ROADWAY PLAN & PROFILE - SHEET 5 OF 5	STA. 72+00.00 TO STA. 77+34.82	3.0	196.8	406.0	0.0	1.4	19.4	1886.5	1794.5	39.6
CONSTRUCTION DETAILS - SHEET 1 OF 5	SPLITTER ISLAND - WEST LEG	-	-	-	-	-	-	-	84.5	40.1
CONSTRUCTION DETAILS - SHEET 2 OF 5	SPLITTER ISLAND - EAST LEG	-	-	-	-	-	-	-	82.0	40.0
CONSTRUCTION DETAILS - SHEET 3 OF 5	SPLITTER ISLAND - SOUTH LEG	-	-	-	-	-	-	-	85.5	40.4
CONSTRUCTION DETAILS - SHEET 4 OF 5	SPLITTER ISLAND - NORTH LEG	-	-	-	-	-	-	-	80.6	39.6
TOTAL		6	516	1600	237	74	61	7192	9391	319

FILE NAME = L:\AR\EC01122401\0 - 06\ROAD_Schedule of Quantities.dwg



USER NAME = Jeff Sedig	DESIGNED - MNB	REVISED -
PLOT SCALE = 1/8" = 1'-0"	DRAWN - MNB	REVISED -
PLOT DATE = 11/12/2012	CHECKED - CMC	REVISED -
	DATE = 10/22/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 1 OF 3 SHEETS STA. - TO STA. -

F.A.U. RTE. 0192	SECTION 06-00153-07-CH	COUNTY LAKE	TOTAL SHEETS 120	SHEET NO. 6
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63682	