

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	004 RECONSTRUCTION	021 TRAFFIC SIGNALS	021 LIGHTING	042 TRAINEES
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	144	144			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	289	289			
20101000	TEMPORARY FENCE	FOOT	6,280	6,280			
20101100	TREE TRUNK PROTECTION	EACH	30	30			
* 20101200	TREE ROOT PRUNING	EACH	30	30			
20101700	SUPPLEMENTAL WATERING	UNIT	30	30			
20200100	EARTH EXCAVATION	CU YD	10,219	10,219			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,615	2,615			
20400800	FURNISHED EXCAVATION	CU YD	563	563			
20800150	TRENCH BACKFILL	CU YD	3,240	3,240			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	7,850	7,850			
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	13,900	13,900			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	275	275			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	275	275			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	275	275			
* 25200110	SODDING, SALT TOLERANT	SQ YD	13,900	13,900			
28000510	INLET FILTERS	EACH	106	106			
30300001	AGGREGATE SUBGRADE IMPROVEMENT	SQ YD	2,615	2,615			
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	16,500	16,500			
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1,795.0	1,795.0			
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	260	260			
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	935	935			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	190	190			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,510	1,510			
40600300	AGGREGATE (PRIME COAT)	TON	29	29			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	130	130			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	40	40			
40600990	TEMPORARY RAMP	SQ YD	40	40			

* SPECIALTY ITEM

FILE NAME = 4185.800-DT1.dwg

USER NAME = PAUL SWIATEK

DESIGNED - BVS

REVISED -

PLOT SCALE = 1" = 0833'

DRAWN - PJS

REVISED -

PLOT DATE = 10/17/2012

CHECKED - KLB

REVISED -

DATE - 10/17/12

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
KENSINGTON ROAD IMPROVEMENTS**

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

FAU

RTE

1295

SECTION

09-00154-00-PV

COUNTY

COOK

TOTAL SHEETS

119

SHEET NO.

05

CONTRACT # 63746

ILLINOIS FED. AID PROJECT