

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	004 RECONSTRUCTION	021 TRAFFIC SIGNALS	021 LIGHTING	042 TRAINEES
67100100	MOBILIZATION	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKINGS	FOOT	3,000	3,000			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	700	700			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9,200	9,200			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,000	3,000			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	600	600			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	530	530			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	500	500			
72000100	SIGN PANEL - TYPE 1	SQ FT	302		302		
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	22		22		
72900200	METAL POST - TYPE B	FOOT	690		690		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	700	700			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,200	9,200			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,000	3,000			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	600	600			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	530	530			
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1	
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1	
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA	FOOT	169		94	75	
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA	FOOT	615		600	15	
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA	FOOT	96		96		
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA	FOOT	148	93		55	
* 81028730	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1-1/4" DIAMETER	FOOT	550			550	
* 81028740	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1-1/2" DIAMETER	FOOT	3,255			3,255	
* 81400100	HANDHOLE	EACH	2		2		
* 81400200	HEAVY-DUTY HANDHOLE	EACH	2	2			
* 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO 8	FOOT	19,660			19,660	
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO 6	FOOT	10,850			10,850	

* SPECIALTY ITEM