

PLAN SURVEYED, PLOTTED, ALIGNED, CHECKED, NOTE BOOK, NO. DATE

PROFILE SURVEYED, PLOTTED, FRAMES CHECKED, STRUCTURE NOTARIS OFF, NO. DATE

PAY ITEM #	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0004	0021	0031	0042	0044
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	68			68		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	81			81		
20100500	TREE REMOVAL, ACRES	ACRE	0.3			0.3		
* 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	50			50		
* 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	50			50		
20200100	EARTH EXCAVATION	CU YD	5,536	5,536				
20200500	EARTH EXCAVATION (WIDENING)	CU YD	1,240	1,240				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,315	2,315				
20800150	TRENCH BACKFILL	CU YD	375	375				
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	23,596			23,596		
21400100	GRADING AND SHAPING DITCHES	FOOT	9,340					9,340
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	293			293		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	293			293		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	293			293		
* 25200110	SODDING, SALT TOLERANT	SQ YD	23,596			23,596		
* 25200200	SUPPLEMENTAL WATERING	UNIT	71			71		
28000500	INLET AND PIPE PROTECTION	EACH	21					21
28000510	INLET FILTERS	EACH	28					28
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	2,315	2,315				
35101500	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	2,781			2,781		
35501321	HOT-MIX ASPHALT BASE COURSE, 9 1/4"	SQ YD	6,001	6,001				
35800713	HOT-MIX ASPHALT BASE COURSE WIDENING, 9 1/4"	SQ YD	3,409	3,409				
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	186	186				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,355	6,355				
40600300	AGGREGATE (PRIME COAT)	TON	127	127				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,311	1,311				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	200	200				
40600990	TEMPORARY RAMP	SQ YD	274	274				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,559	3,559				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	28,770	28,770				
42400800	DETECTABLE WARNINGS	SQ FT	360	360				

PAY ITEM #	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0004	0021	0031	0042	0044
44000180	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	22,101	22,101				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,008	1,008				
44000600	SIDEWALK REMOVAL	SQ FT	8,795		8,795			
44004250	PAVED SHOULDER REMOVAL	SQ YD	3,510	3,510				
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	100	100				
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	174	174				
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	219	219				
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	349	349				
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	4,695	4,695				
50105220	PIPE CULVERT REMOVAL	FOOT	344					344
542A0220	PIPE CULVERTS, CLASS A, TYPE I 15"	FOOT	140					140
542A0223	PIPE CULVERTS, CLASS A, TYPE I 18"	FOOT	20					20
542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	95					95
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4					4
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2					2
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1					1
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	1					1
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1					1
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	80					80
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	49					49
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	70					70
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	80					80
55100500	STORM SEWER REMOVAL 12"	FOOT	109					109
60107600	PIPE UNDERDRAINS 4"	FOOT	70					70
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	3					3
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	2					2
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1					1
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3					3
60237480	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	3					3
60255500	MANHOLES TO BE ADJUSTED	EACH	9					9
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1					1

* = SPECIALTY ITEM