

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				RECONSTRUCTION	TRAINEES		
				CAPACITY ADDED 0003	CAPACITY ADDED 0042		
28000305	TEMPORARY DITCH CHECKS	FOOT	100	100			
28000400	PERIMETER EROSION BARRIER	FOOT	4,365	4,365			
28000500	INLET AND PIPE PROTECTION	EACH	26	26			
28000510	INLET FILTERS	EACH	45	45			
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	1,455	1,455			
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	13,415	13,415			
35600730	HOT-MIX ASPHALT BASE COURSE WIDENING, 13 1/2"	SQ YD	172	172			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9,708	9,708			
40600300	AGGREGATE (PRIME COAT)	TON	18	18			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	306	306			
40600895	CONSTRUCTING TEST STRIP	EACH	4	4			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	333	333			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	190	190			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	408	408			

FILE NAME = ... \MtlCo-9185629-shs004-S002.dgn
PLOT TIME = 5:19:04 PM
PLOT DATE = 9/25/2012

DESIGNED - MC
DRAWN - AP
CHECKED - GAO
DATE - 9/28/2012
REVISED -
REVISED -
REVISED -
REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SCALE: N/A
SHEET NO. 2 OF 8 SHEETS
STA. N/A TO STA. N/A

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1600	06-00169-14-FP	WILL	55	4
			CONTRACT NO. 63752	
ILLINOIS FED. AID PROJECT				