



NOTE:  
 ALL CONSTRUCTION TO BE DONE ACCORDING TO STATE OF ILLINOIS "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION".

ALL GROUND AREAS DISTURBED SHALL BE RESEEDED AND MULCHED OR JUTE MATTED AS SOON AFTER CONSTRUCTION AS POSSIBLE.

REMOVE AND REPLACE SIDEWALK AS NECESSARY TO PROVIDE ADEQUATE TRANSITION TO EXISTING GRADES.

CUT OUT DIRT ON SHOULDER. INSTALL AGGREGATE SUBGRADE, 12", AND PAVE WITH 2 1/2" HMA SURFACE COURSE, MIX C N50 TO THE NEW PROPERTY LINE.

**DRIVEWAY DETAIL**

FILE NAME = ...\\wllco-9185609-ah1034-Detail.dgn	DESIGNED - CG	REVISED -	 800 W. FULLTOWN ST. CHICAGO, ILLINOIS 60611-1539 TEL: 312.484.9100 FAX: 312.688.1217 WEB: www.sepstein.com	<b>STATE OF ILLINOIS          DEPARTMENT OF TRANSPORTATION</b>	<b>DRIVEWAY DETAILS</b>				F.A.U. RTE. 1600	SECTION 06-00169-14-FP	COUNTY WILL	TOTAL SHEETS 55	SHEET NO. 34
PLOT TIME = 5:58:12 PM	CHECKED - GAO	REVISED -							SCALE: N/A	SHEET NO. 1	OF 1	SHEETS	STA. N/A
PLOT DATE = 9/25/2012	DATE - 9/28/2012	REVISED -							ILLINOIS FED. AID PROJECT				