

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 0004	SAFETY 0021	NON PARTICIPATING
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	162	162	-	-
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	74	74	-	-
20101100	TREE TRUNK PROTECTION	EACH	16	13	-	3
* 20101200	TREE ROOT PRUNING	EACH	16	13	-	3
20200100	EARTH EXCAVATION	CU YD	3,753	3,109	-	644
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,260	2,201	-	59
20800150	TRENCH BACKFILL	CU YD	288	227	-	61
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	4,556	4,556	-	-
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5,598	5,011	-	587
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72	64	-	8
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72	64	-	8
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72	64	-	8
* 25200110	SODDING, SALT TOLERANT	SQ YD	5,598	5,011	-	587
* 25200200	SUPPLEMENTAL WATERING	UNIT	59	52	-	7
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	117	104	-	13
28000400	PERIMETER EROSION BARRIER	FOOT	314	314	-	-
28000510	INLET FILTERS	EACH	81	73	-	8
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	629	629	-	-
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	4,141	4,141	-	-
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	8,493	6,337	-	2,156
35300200	PORTLAND CEMENT CONCRETE BASE COURSE 7"	SQ YD	14	14	-	-
35300205	PORTLAND CEMENT CONCRETE BASE COURSE 7 1/4"	SQ YD	65	65	-	-
35501304	HOT-MIX ASPHALT BASE COURSE, 5"	SQ YD	559	-	-	559
35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	440	440	-	-
35501313	HOT-MIX ASPHALT BASE COURSE, 7 1/4"	SQ YD	2,153	2,153	-	-
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	2,715	1,781	-	934
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	13	-	2
40600300	AGGREGATE (PRIME COAT)	TON	64	59	-	5
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	4	-	1
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	827	777	-	50

* INDICATES SPECIALTY ITEM

CONTRACT NO. 0348/1352
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 0348-0001-0001-0001
 DATE 8/23/12



DESIGNED - DSH	REVISED - 10-12-12 PER 100T
DRAWN - MAC	REVISED - 10-29-12 PER VILLAGE
CHECKED - TLH	REVISED - 11-29-12 PER VILLAGE
DATE - 8/23/12	FILE - 110025-12-S00.dht

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: STA. TC STA.

F.A.P./F.A.U. RYE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0348/1352	05-00163-09-CH	COOK	109	4
C-91-070-06		CONTRACT NO. 63756		
HLY. ROAD DIST. NO. 1 (ILLINOIS)		FED. AID PROJECT F-0348(35)		