

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 0004	SAFETY 0021	NON PARTICIPATING
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	243	243	-	-
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	190	190	-	-
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	-	1	-
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1807	-	1,762	45
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	56	-	56	-
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	1110	-	1,110	-
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	476	-	476	-
* 81400100	HANDHOLE	EACH	5	-	5	-
* 81400200	HEAVY-DUTY HANDHOLE	EACH	4	-	3	1
* 81400300	DOUBLE HANDHOLE	EACH	2	-	2	-
* 81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	40	-	40	-
* 81603110	UNIT DUCT, 600V, 4-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	4195	-	4,195	-
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	248	-	248	-
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	26	3	23	-
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	23	-	23	-
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1	-	1	-
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2962	-	2,962	-
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1224	-	836	388
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1598	-	1,196	402
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	959	-	856	103
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1706	-	1,401	305
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2148	-	1,788	360
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	53	-	53	-
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT, GROUNDING CONDUCTOR, NO. 6 1C	FOOT	516	-	516	-
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4	-	4	-
* 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1	-	1	-
* 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1	-	1	-
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1	-	1	-
* 87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1	-	-	1
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16	-	16	-

* INDICATES SPECIALTY ITEM

C:\WORK\8076\8076.DWG BY: DANIEL A. WOODMAN, INC. STATE OF ILLINOIS PROFESSIONAL LICENSE #001-070-060
 LICENSE NO. 001-070-060 EXPIRES 07/31/2013
 07/31/2013
 8/23/12
 110025-12-500.sht



DESIGNED - DSH	REVISED - 10-12-12 PER IDOT
DRAWN - MAC	REVISED -
CHECKED - TLH	REVISED -
DATE - 8/23/12	FILE - 110025-12-500.sht

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: | STA. TO STA.

F.A.P./F.A.U. RT.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0348/1352	05-00160-00-CH	COOK	109	8
C-91-070-06		CONTRACT NO. 63756		
FFD, ROAD DIST. NO. 1 (ILLINOIS)		FFD, AID PROJECT F-0348(3)		