

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 0004	SAFETY 0021	NON PARTICIPATING
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	-	4	-
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10	-	10	-
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	39	-	24	15
* 87900200	DRILL EXISTING HANDHOLE	EACH	1	-	1	-
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	5	-	4	1
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3	-	2	1
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	5	-	4	1
* 88030220	SIGNAL HEAD, LED, 2-FACE, 5 SECTION, BRACKET MOUNTED	EACH	1	-	1	-
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8	-	6	2
* 88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	10	-	8	2
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	9	-	7	2
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1,010	-	807	203
* 88700200	LIGHT DETECTOR	EACH	2	-	2	-
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1	-	1	-
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	-	6	2
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	-	1	-
* 89500120	REMOVE EXISTING SERVICE INSTALLATION	EACH	1	-	1	-
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	10,253	-	10,253	-
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	-	1	-
* 89502380	REMOVE EXISTING HANDHOLE	EACH	12	-	12	-
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	17	9	8	-
* A2004824	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	EACH	10	9	-	1
* A2005024	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 3" CALIPER, BALLED AND BURLAPPED	EACH	11	10	-	1
* B2006124	TREE, SYRINGA PEKINENSIS MORTON (CHINA SNOW PEKING LILAC), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	4	-	1
* C2005818	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 18" WIDTH, BALLED AND BURLAPPED	EACH	20	20	-	-
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	216	216	-	-
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-	-
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	259	259	-	-
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	8	-	8	-
* Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1	-	1	-

* INDICATES SPECIALTY ITEM

DESIGNED BY: DSH
 DRAWN BY: MAC
 CHECKED BY: TLH
 DATE: 8/23/12
 REVISED - 10-12-12 PER IDOT
 REVISED - 10-29-12 PER VILLAGE
 FILE - J10025-12-S00.eht
 STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION
 CONTRACT NO. 63756
 SECTION 05-00160-00-CH
 COUNTY COOK
 SHEET NO. 9
 TOTAL SHEETS 109
 FED. ROAD DIST. NO. 1 ILLINOIS
 FED. AID PROJECT F-0348(03)



DESIGNED	DSH	REVISED	- 10-12-12 PER IDOT
DRAWN	MAC	REVISED	- 10-29-12 PER VILLAGE
CHECKED	TLH	REVISED	-
DATE	8/23/12	FILE	J10025-12-S00.eht

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.P./F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0348/1352	05-00160-00-CH	COOK	109	9
C-91-073-06		CONTRACT NO. 63756		
FED. ROAD DIST. NO. 1 ILLINOIS		FED. AID PROJECT F-0348(03)		