



END IMPROVEMENTS AT STA 2081+05

SEE BATAVIA ROAD AND WARRENVILLE ROAD INTERSECTION DETAIL FOR ADDITIONAL SIGNS AND PAVEMENT MARKING INFORMATION

LEGEND

- EXISTING CONCRETE SIDEWALK OR DRIVEWAY TO REMAIN IN PLACE
- SIDEWALK OR PCC DRIVEWAY REMOVAL AND REPLACEMENT
- HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT
- BRICK
- (A) HOT-MIX ASPHALT DRIVEWAY AND PAVEMENT REMOVAL STABILIZED DRIVEWAYS, 10"
- (B) DRIVEWAY PAVEMENT REMOVAL AND PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7"
- (C) BRICK PAVER REMOVAL AND REPLACEMENT
- (D) SIDEWALK REMOVAL AND PORTLAND CEMENT CONCRETE SIDEWALK, 5"
- (E) SIDEWALK REMOVAL AND PORTLAND CEMENT CONCRETE SIDEWALK, 7"
- (F) DETECTABLE WARNINGS
- (G) PORTLAND CEMENT CONCRETE SIDEWALK, 5"
- (H) PORTLAND CEMENT CONCRETE SIDEWALK, 7"
- (I) HOT-MIX ASPHALT DRIVEWAY AND PAVEMENT REMOVAL STABILIZED DRIVEWAY PAVEMENT

- NOTES:**
- THE CITY OF WARRENVILLE SHALL REMOVE, REPLACE, RELOCATE AND FURNISH ALL SIGNS REQUIRED.
 - RECESSED REFLECTIVE PAVEMENT MARKERS PLACEMENT AND COLOR SHALL CONFORM TO IDOT DISTRICT 1 HIGHWAY STANDARD TC-11

Plotted: October 16, 2012 @ 3:24 PM By: Jim Schmidt - Tab: 19 Drive - 22x34

COPYRIGHT © 2012 ENGINEERING ENTERPRISES, INC.

Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60554
630.466.6700 / www.eeweb.com

USER NAME =	DESIGNED - SWM/TVW	REVISED -
PLOT SCALE =	DRAWN - KKP/CLN/JPS	REVISED -
PLOT DATE =	CHECKED - JRL	REVISED -
	DATE - 8/24/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING, SIGNING, SIDEWALK AND DRIVEWAY PLAN

SCALE: N/A SHEET NO. 3 OF 3 SHEETS STA. 2075+00 TO STA. 2081+00

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3553	10-00031-00-RS	DUPAGE	29	19
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 63758	
FED. AID PROJECT - M-90038661				

Path: H:\5056\F03\W1003\DWG\DWG_FINAL_ENG\W1003-Drive