

SEEDING AND EROSION CONTROL SCHEDULE (1 OF 2)											
LOCATION	SEEDING, CLASS 1A	SEEDING, CLASS 2A	SEEDING, CLASS 4A	SEEDING, CLASS 5A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	TEMPORARY EROSION CONTROL SEEDING	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	MULCH, METHOD 2
	ACRE	ACRE	ACRE	ACRE	POUND	POUND	POUND	POUND	SQ YD	SO YD	ACRE
US ROUTE 34											
STA 512+00.00 TO STA 528+92.63	0.00	1.81	5.70	5.70	163	163	163	751	13,022	0	7.51
STA 528+92.63 TO STA 555+73.12	0.00	4.22	10.58	10.58	380	380	380	1,480	25,424	0	14.80
STA 555+73.12 TO STA 611+78.78	0.00	7.71	15.37	15.37	694	694	694	2,308	32,356	0	23.08
STA 611+78.78 TO STA 693+89.92	0.00	11.36	23.22	23.22	1,022	1,022	1,022	3,458	42,776	0	34.58
STA 693+89.92 TO STA 721+25.00	0.00	4.08	6.36	6.36	367	367	367	1,044	21,128	0	10.44
STA 721+25.00 TO STA 758+00.00	0.00	4.10	12.16	12.16	369	369	369	1,626	41,355	568	16.26
STA 758+00.00 TO STA 776+84.33	0.00	2.36	7.84	7.84	212	212	212	1,020	27,391	903	10.20
STA 776+84.33 TO STA 803+29.29	0.00	4.08	8.83	8.83	367	367	367	1,291	15,350	0	12.91
STA 803+29.29 TO STA 830+00.00	0.00	3.19	5.66	5.66	287	287	287	885	12,817	0	8.85
IL ROUTE 94 / 116											
STA 5+00.00 TO STA 26+70.22	2.35	0.63	4.27	4.27	268	268	268	725	11,520	0	7.25
STA 26+70.22 TO STA 46+00.00	0.00	1.26	5.50	5.50	113	113	113	676	10,835	0	6.76
RAMP A											
STA 6+50.00 TO STA 19+50.00	0.00	0.70	4.30	4.30	63	63	63	500	6,973	0	5.00
RAMP B											
STA 2+00.00 TO STA 11+50.00	0.00	0.59	3.59	3.59	53	53	53	418	6,307	0	4.18
RAMP C											
STA 7+00.00 TO STA 21+97.59	0.00	0.64	5.03	5.03	58	58	58	567	6,840	0	5.67
RAMP D											
STA 0+23.09 TO STA 11+00.00	0.00	0.52	3.39	3.39	47	47	47	391	6,662	0	3.91
SUBTOTAL 1	2.35	47.25	121.80	121.80	4,463	4,463	4,463	17,140	280,756	1,471	171.40

*MULTIPLY BASE TOTAL BY 39 TO ACCOUNT FOR RESEEDING EVERY TWO WEEKS FOR 2 GROWING SEASONS (MARCH 1 - NOVEMBER 30)

△ REVISIED SHEET 1-8-13

FILE NAME * D:\68409-SHT-44-45-SEEDING.dgn	USER NAME * mikel	DESIGNED - DBS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES US ROUTE 34			F.A.P. RTE. 313	SECTION 7-2 & 6-1	COUNTY HENDERSON	TOTAL SHEETS 976	SHEET NO. 73
	PLOT SCALE = 100.0000' / in.	DRAWN - PSBA	REVISED -		SCALE: N.A.	SHEET NO. 44 OF 51 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE = 1/9/2013	CHECKED - CSB	REVISED -									
		DATE - 10/2012	REVISED -									