

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

OLD OLD OLD NEW NEW

ILLINOIS DEPARTMENT OF TRANSPORTATION

80% FED.
20% STATE

SUMMARY OF QUANTITIES

011-0002	011-0002	011-2008		
LOSEC, 01	LOSEC, 01	LOSEC, 02	LOSEC, 03	LOSEC, 04

CONSTRUCTION TYPE CODE

CHRISTIAN COUNTY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0001 RURAL	BRIDGE 0013 S.N. 011-0037	BRIDGE 0008 S.N. 011-0038	CULVERT 0008 S.N. 011-2504	BRIDGE 0008 S.N. 011-3362	CULVERT 0008 S.N. 011-3413	LIGHTING 0021
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	199	199						
40600990	TEMPORARY RAMP	SQ YD	1,000	1,000						
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	891	891						
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	767	767						
40603515	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	363	363						
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,318	1,318						
40701866	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/4"	SQ YD	7,623	7,623						
40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	SQ YD	140,247	140,247						
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	22	22						
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	2,143	2,143						
44000100	PAVEMENT REMOVAL	SQ YD	44,313	44,313						
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	5,832	5,832						
44000600	SIDEWALK REMOVAL	SQ FT	311	311						
44004000	PAVED DITCH REMOVAL	FOOT	3,532	3,532						

10/10/2012

PUBLIC WORKS SOUTH PLANS MANAGED BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION

REVISIONS	
NAME	DATE
SEB	10/10/12

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHEET 5 OF 21
 FAP 322 (US 51)
 SECTION 11-13
 CHRISTIAN COUNTY

SCALE: NONE
 DATE: DRAWN BY: SEB
 CHECKED BY: SRW