72961

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

				OLD	OLD	OLD	NEW	NEW	
					80% FED. 20% STATE				
				011-0002	011-0002	011-2008			
				L05EC,01	L05EC,01	L05EC,02	L05EC,03	L05EC,04	
				CONSTRUCTION TYPE CODE					
				CHRISTIAN COUNTY					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0001 RURAL	BRIDGE 0013 S.N. 011-0037	BRIDGE 0008 S.N. 011-0038	CULVERT 0008 S.N. 011-2504	BRIDGE 0008 S.N. 011-3362	CULVERT 0008 S.N. 011-3413	LIGHTING 0021
50800105	REINFORCEMENT BARS	POUND	118,895	5,925			91,150		21,820	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	190,350		54,490	94,060		41,800		
50800515	BAR SPLICERS	EACH	132		44	88				
50800530	MECHANICAL SPLICERS	EACH	686		686					
50901050	STEEL RAILING, TYPE SM	FOOT	294					294		
51201600	FURNISHING STEEL PILES HP12X53	FOOT	2,041		804			1,237		
51201610	FURNISHING STEEL PILES HP12X63	FOOT	1,436			1,436				
51202305	DRIVING PILES	FOOT	3,477		804	1,436		1,237		
51203600	TEST PILE STEEL HP12X53	EACH	2					2		
51203610	TEST PILE STEEL HP12X63	EACH	2			2				
51204650	PILE SHOES	EACH	46			24		22		
51500100	NAME PLATES	EACH	5		1	1	1	1	1	
54003000	CONCRETE BOX CULVERTS	CU YD	665.9				523.7		142.2	
54011006	PRECAST CONCRETE BOX CULVERTS 10' X 6'	FOOT	88	88						
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	128	128						

REVISIONS	
NAME	DATE
SEB	10/10/12

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 8 OF 21
FAP 322 (US 51)
SECTION 11-13
CHRISTIAN COUNTY

SCALE: NONE DRAWN BY SEB
DATE CHECKED BY SRW

10/10/2012

D:\Bifiles\18187325\SOUTH_PLANS_NEW\CADD Sheets\0622961sht1-Summary.dgn