72961

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	15
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

					OLD	OLD	OLD	NEW	NEW	
					80% FED. 20% STATE					
					011-0002	011-0002	011-2008			
					L05EC, 01	L05EC, 02	L05EC, 02	L05EC, 03	L05EC, 04	
					CONSTRUCTION TYPE CODE					
					CHRISTIAN COUNTY					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0001 RURAL	BRIDGE 0013 S.N. 011-0037	BRIDGE 0008 S.N. 011-0038	CULVERT 0008 S.N. 011-2504	BRIDGE 0008 S.N. 011-3362	CULVERT 0008 S.N. 011-3413	LIGHTING 0021
61133400	FIELD TILE JUNCTION VAULTS, 5' DIA.	EACH	4	4						
61140000	STORM SEWERS (SPECIAL), 8"	FOOT	3,000	3,000						
61140100	STORM SEWERS (SPECIAL), 10"	FOOT	500	500						
61140200	STORM SEWERS (SPECIAL), 12"	FOOT	3,000	3,000						
61140600	STORM SEWERS (SPECIAL), 18"	FOOT	500	500						
61140900	STORM SEWERS (SPECIAL), 24"	FOOT	500	500						
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1,206.3	1,206.3						
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6						
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4						
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8						
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2						
63200310	GUARDRAIL REMOVAL	FOOT	1,188	1,188						
63500105	DELINEATORS	EACH	228	228						
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	81,059	81,059						

*SPECIALTY ITEM

REVISIONS	
NAME	DATE
SEB	10/10/12

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 12 OF 21
FAP 322 (US 51)
SECTION 11-13
CHRISTIAN COUNTY

SCALE: NONE DRAWN BY SEB
DATE CHECKED BY SRW

10/19/2012

D:\Pif\Jobs\78329\SOUTH PLAZA SEW\CADD Sheets\072961-Ax-Summary.dgn