72961

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	35
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PIPE UNDERDRAIN SCHEDULE

SOUTHBOUND OUTSIDE EDGE OF PAVEMENT

		60107600		60108100		60100060	78001120
PIPE UNDERDRAIN 4"			PIPE UNDERDRAIN 4" (SPECIAL)			CONCRETE HEADWALL	PAINT PAVEMENT MARKING 5"
BEGINNING STATION	ENDING STATION	LENGTH FOOT	OUTLET STATION	LENGTH FOOT	CONNECT TO STRUCTURE	EACH	FOOT
FAP 322 (US 51)							
331+00	333+50	250.0	333+50	19.9		1	2.0
333+50	337+00	350.0	337+00		Y		
337+00	341+00	400.0	337+00		Y		
341+00	346+00	500.0	341+00		Y		
346+00	350+20	420.0	346+00	20.4		1	2.0
350+20	352+00	180.0	352+00		Y		
352+00	357+00	500.0	357+00		Y		
357+00	360+06	306.0	357+00		Y		
372+46	375+00	254.0	375+00	22.8		2	2.0
375+00	378+50	350.0	375+00				
378+50	382+00	350.0	378+50	21.3		1	2.0
382+00	386+00	400.0	386+00	21.3		1	2.0
386+00	390+00	400.0	390+00	22.8		2	2.0
390+00	393+50	350.0	390+00				
393+50	397+00	350.0	393+50	19.8		1	2.0
397+00	400+50	350.0	397+00	21.3		1	2.0
400+50	404+50	427.5	404+50	21.2		1	2.0
404+50	408+54	404.0	408+54		Y		
408+54	411+00	246.0	408+54		Y		
411+00	413+82	282.0	411+00	19.8		1	2.0
415+82	420+00	418.0	415+82	14.6		1	2.0
420+00	424+72	472.0	420+00	14.6		1	2.0
424+72	429+00	428.0	429+00	19.8		1	2.0
429+00	433+00	400.0	433+00	19.8		1	2.0
433+00	436+98	398.0	436+98	19.8		2	2.0
436+98	441+00	402.0	436+98				
441+00	445+00	400.0	441+00	19.8		1	2.0
445+00	449+09	409.0	445+00	19.8		1	2.0
449+09	453+00	391.0	453+00	22.2		1	2.0
453+00	457+00	400.0	457+00	19.8		1	2.0
457+00	461+00	400.0	461+00	19.8		1	2.0
461+00	465+98	498.0	465+98	19.8		1	2.0
468+00	469+11	111.0	469+11	14.6		1	2.0
470+95	473+30	235.0	473+30	23.6		2	2.0
473+30	478+00	470.0	473+30				
478+00	483+00	500.0	478+00	19.8		1	2.0
483+00	488+00	500.0	483+00	19.8		1	2.0
488+00	492+63	463.0	488+00	19.8		1	2.0
493+63	498+00	437.0	498+00	19.8		1	2.0
498+00	502+50	450.0	502+50	19.8		1	2.0
502+50	507+00	450.0	507+00	19.8		1	2.0
507+00	511+36	436.0	511+36	21.6		2	2.0
511+36	516+00	464.0	511+36				
516+00	520+49	449.0	516+00	19.8		1	2.0
522+50	525+19	269.0	522+50	18.9		1	2.0
525+19	530+00	481.0	530+00	27.3		1	2.0
530+00	534+50	450.0	534+50	19.8		1	2.0
534+50	539+00	450.0	539+00		Y		
539+00	542+50	350.0	542+50	19.8		1	2.0
542+50	546+38	388.0	546+38	19.8		1	2.0
547+82	552+00	418.0	552+00	19.8		1	2.0
552+00	556+00	400.0	556+00	19.8		1	2.0
556+00	560+00	400.0	560+00	19.8		1	2.0
560+00	564+66	466.0	564+55	22.1		1	2.0
SUBTOTALS		21122.5		805.9		45	80.0

PIPE UNDERDRAIN SCHEDULE

SOUTHBOUND INSIDE EDGE OF PAVEMENT

		60107600		60108100		60100060	78001120
PIPE UNDERDRAIN 4"			PIPE UNDERDRAIN 4" (SPECIAL)			CONCRETE HEADWALL	PAINT PAVEMENT MARKING 5"
BEGINNING STATION	ENDING STATION	LENGTH FOOT	OUTLET STATION	LENGTH FOOT	CONNECT TO STRUCTURE	EACH	FOOT
FAP 322 (US 51)							
331+00	337+00	600.0	337+00		Y		
337+00	341+00	400.0	337+00		Y		
341+00	343+38	238.0	341+00		Y		
358+60	359+84	124.0	358+60	15.9		1	2.0
361+68	362+15	47.0	362+15	15.5	Y		
362+15	367+00	485.0	362+15		Y		
367+00	372+00	500.0	372+00	18.5		1	2.0
372+00	375+00	300.0	375+00	22.0	Y		
375+00	380+65	565.0	375+00				
382+45	386+00	355.0	386+00	12.4	Y	1	2.0
386+00	390+00	400.0	390+00	22.0	Y		
390+00	393+50	350.0	390+00				
393+50	397+00	350.0	393+50	18.5		1	2.0
397+00	400+50	350.0	397+00	18.5		1	2.0
400+50	404+50	427.5	404+50	18.8	Y	1	2.0
404+50	408+54	404.0	408+54		Y		
408+54	413+95	541.0	408+54		Y		
415+93	420+00	407.0	415+93	15.0			
420+00	424+72	472.0	420+00	12.2		1	2.0
424+72	429+00	428.0	429+00	16.8		1	2.0
429+00	433+00	400.0	433+00	16.8		1	2.0
433+00	436+98	398.0	436+98	16.8		2	2.0
436+98	441+00	402.0	436+98				
441+00	445+00	400.0	441+00	16.8		1	2.0
445+00	450+00	500.0	445+00	19.4		1	2.0
451+80	456+50	470.0	456+50	12.7		1	2.0
456+50	461+00	450.0	461+00	16.8	Y	1	2.0
461+00	466+09	509.0	466+09	19.0			
467+90	469+25	135.0	469+25	10.9	Y	1	2.0
471+08	473+30	222.0	473+30	20.5	Y		
473+30	478+00	470.0	473+30				
478+00	483+00	500.0	478+00	16.8		1	2.0
483+00	488+00	500.0	483+00	16.8		1	2.0
488+00	492+63	463.0	488+00	16.8	Y	1	2.0
492+63	496+52	389.0	496+52	19.0			
498+32	502+50	418.0	502+50	12.2		1	2.0
502+50	507+00	450.0	507+00	18.1	Y	1	2.0
507+00	511+36	436.0	511+36	23.0			
511+36	516+00	464.0	511+36				
516+00	520+62	462.0	516+00	17.3	Y	1	2.0
522+61	525+19	258.0	522+61	15.0			
525+19	530+00	481.0	530+00	19.3		1	2.0
530+00	534+50	450.0	534+50	16.8	Y	1	2.0
534+50	539+00	450.0	539+00				
539+00	542+50	350.0	542+50	15.4	Y	1	2.0
542+50	546+10	360.0	546+10	19.0			
547+90	552+00	410.0	552+00	12.7		1	2.0
552+00	556+00	400.0	556+00	18.4		1	2.0
556+00	560+00	400.0	560+00	18.2		1	2.0
560+00	564+66	466.0	564+66	18.8		1	2.0
569+00	572+75	375.0	569+00	18.3		1	2.0
SUBTOTALS		20581.5		667.7		30	58.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SHEET 11 OF 22
FAP 322 (US 51)
SECTION 11-13
CHRISTIAN COUNTY

SCALE: DRAWN BY EBB
DATE 4/11 CHECKED BY

10/5/2012

Q:\Files\010329\SOUTH PLANS NEW\CADD Sheets\0672961-sht-Schedules.dgn