

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	38
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SIGNING SCHEDULE

72000100 72000200 72800100 73000100

STATION	LANE	SIDE	FACING	SIGN NUMBER (MUTCD)	SIZE (IN)		MESSAGE	NUMBER OF POSTS	SIGN PANEL		TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT
					W	H			TYPE 1	TYPE 2		
											SO FT	
EX US 51												
194+83		RT	SOUTH	W6-1	36	36	DIVIDED HIGHWAY SYMBOL	2	9.0		37.2	
195+35		LT	SOUTH	W14-3	48	36	NO PASSING ZONE	2	6.0		34.0	
CROSSOVER "A"												
55+55		LT	NORTH	W6-3	36	36	TWO WAY TRAFFIC SYMBOL	2	9.0		37.2	
55+55		RT	SOUTH	R4-7	36	48	KEEP RIGHT SYMBOL	2		12.0	37.2	
			NORTH	W6-3	36	36	TWO WAY TRAFFIC SYMBOL		9.0			
58+00		LT	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
59+00		LT	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
60+00		LT	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
61+00		LT	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
62+00		LT	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
63+00		LT	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
64+00		LT	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
65+00		LT	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
FAP 322 (US 51)												
341+85	SB	MEDIAN	WEST	R6-1R	36	12	ONE WAY RIGHT	1	3.0		15.7	
342+30	NB	OUTSIDE	SOUTH	R2-1	48	60	SPEED LIMIT 65 MPH	2		20.0		44.0
	NB	OUTSIDE	SOUTH	R2-1101	30	30	MINIMUM 45 MPH		6.3			
344+50	SB	MEDIAN	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
345+50	SB	MEDIAN	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
346+50	SB	MEDIAN	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
347+50	SB	MEDIAN	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
348+50	SB	MEDIAN	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
349+50	SB	MEDIAN	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
350+50	SB	MEDIAN	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
351+50	SB	MEDIAN	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
352+50	SB	MEDIAN	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
353+50	SB	MEDIAN	NORTH	W1-B	24	30	CHEVRON	1	5.0		14.5	
347+72	NB	MEDIAN	EAST	R6-1R	36	12	ONE WAY RIGHT	1	3.0		15.7	
347+73	SB	MEDIAN	WEST	R6-1R	36	12	ONE WAY RIGHT	1	3.0		15.7	
351+30	NB	OUTSIDE	SOUTH	W2-1	36	36	SIDE ROAD SYMBOL	2	9.0		40.0	
			SOUTH	W16-8	24	12	E 600N RD		2.0			
351+30	NB	MEDIAN	SOUTH	W2-1	36	36	SIDE ROAD SYMBOL	2	9.0		40.0	
			SOUTH	W16-8	24	12	E 600N RD		2.0			
353+15	NB	MEDIAN	SOUTH	R3-1100L	36	36	LEFT TURN LANE	2	9.0		38.0	
			SOUTH	M6-2L	21	15	ARROW LEFT		2.2			
352+95	NB	OUTSIDE	SOUTH	R3-1100R	36	36	RIGHT TURN LANE	2	9.0		38.0	
			SOUTH	M6-2R	21	15	ARROW RIGHT		2.2			
357+30	NB	MEDIAN	NORTH	R5-1α	36	24	WRONG WAY	1	6.0		16.7	
357+30	NB	OUTSIDE	NORTH	R5-1α	36	24	WRONG WAY	1	6.0		16.7	
359+00	SB	OUTSIDE	NORTH	W4-2L	48	48	LEFT LANE ENDS SYMBOL W/ FLAG	2		16.0	40.0	
			NORTH	W16-2αP	24	12	500 FT		2.0			
359+00	SB	MEDIAN	NORTH	W4-2L	48	48	LEFT LANE ENDS SYMBOL W/ FLAG	2		16.0	40.0	
			NORTH	W16-2αP	24	12	500 FT		2.0			
359+85	NB	MEDIAN	NORTH	R5-1	36	36	DO NOT ENTER	2	9.0		35.4	
359+85	NB	OUTSIDE	NORTH	R5-1	36	36	DO NOT ENTER	2	9.0		35.4	
360+40	SB	MEDIAN	WEST	R1-2	36	36	YIELD	1	3.9		17.7	
			WEST	R6-1L	36	12	ONE WAY LEFT		3.0			
361+60	NB	MEDIAN	EAST	R1-2	36	36	YIELD	1	3.9		17.7	
			EAST	R6-1L	36	12	ONE WAY LEFT		3.0			
362+20	SB	MEDIAN	SOUTH	R5-1	36	36	DO NOT ENTER	2	9.0		35.4	
362+20	SB	OUTSIDE	SOUTH	R5-1	36	36	DO NOT ENTER	2	9.0		35.4	
362+20	SB	OUTSIDE	EAST	I2-1100	12	18	RESTORATION AREA	1	1.5		11.0	
			EAST	I2-1104	12	6	NO MOWING OR SPRAYING		0.5			
363+17	NB	OUTSIDE	WEST	I2-1100	12	18	RESTORATION AREA	1	1.5		11.0	
			WEST	I2-1104	12	6	NO MOWING OR SPRAYING		0.5			
364+00	SB	OUTSIDE	NORTH	R2-1	48	60	SPEED LIMIT 55 MPH W/ FLAG	2		20.0	39.4	
364+00	SB	MEDIAN	NORTH	R2-1	48	60	SPEED LIMIT 55 MPH W/ FLAG	2		20.0	39.4	
365+45	SB	OUTSIDE	SOUTH	R5-1α	36	24	WRONG WAY	1	6.0		16.7	
365+45	SB	MEDIAN	SOUTH	R5-1α	36	24	WRONG WAY	1	6.0		16.7	
368+50	SB	OUTSIDE	EAST	I2-1100	12	18	RESTORATION AREA	1	1.5		11.0	
			EAST	I2-1104	12	6	NO MOWING OR SPRAYING		0.5			
369+03	SB	OUTSIDE	NORTH	R3-1100R	36	36	RIGHT TURN LANE	2	9.0		38.0	
			NORTH	M6-2R	21	15	ARROW RIGHT		2.2			
368+83	SB	MEDIAN	NORTH	R3-1100L	36	36	LEFT TURN LANE	2	9.0		38.0	
			NORTH	M6-2L	21	15	ARROW LEFT		2.2			
369+50	NB	OUTSIDE	WEST	I2-1100	12	18	RESTORATION AREA	1	1.5		11.0	
			WEST	I2-1104	12	6	NO MOWING OR SPRAYING		0.5			
370+00	SB	OUTSIDE	NORTH	W4-2L	48	48	LEFT LANE ENDS SYMBOL W/ FLAG	2		16.0	40.0	
			NORTH	W16-2αP	24	12	1600 FT		2.0			
370+00	SB	MEDIAN	NORTH	W4-2L	48	48	LEFT LANE ENDS SYMBOL W/ FLAG	2		16.0	40.0	
			NORTH	W16-2αP	24	12	1600 FT		2.0			
371+30	SB	OUTSIDE	NORTH	W2-1	36	36	SIDE ROAD SYMBOL	2	9.0		40.0	
			NORTH	W16-8	24	12	NO MOWING OR SPRAYING		0.5			
371+30	SB	MEDIAN	NORTH	W2-1	36	36	SIDE ROAD SYMBOL	2	9.0		40.0	
			NORTH	W16-8	24	12	E 600N RD		2.0			
375+00	SB	OUTSIDE	EAST	I2-1100	12	18	RESTORATION AREA	1	1.5		11.0	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 SHEET 14 OF 22
 FAP 322 (US 51)
 SECTION 11-13
 CHRISTIAN COUNTY

SCALE: DATE 4/11 DRAWN BY EBB CHECKED BY

10/5/2012

D:\Files\0103291\South PLANS NEW\CAD\ Sheets\06\2\051\ant-Schedule.dgn