

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	42
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STAGE CONSTRUCTION STRIPING SCHEDULE

STAGE	STATION TO STATION	LANE	SIDE	PAINT PAVEMENT MARKINGS					PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKERS	PAVEMENT MARKERS REMOVAL
				LINE 5" YELLOW	LINE 5" WHITE	LINE 6" WHITE	LINE 24" WHITE	L & S WHITE			
				FOOT							
STAGE 1A	US 51 RELOCATION 98+00 110+95		LT		1295.0						
				CL	2590.4				215.8		
				RT		1295.0					
STAGE 1B	US 51 RELOCATION 98+00 110+95		LT		811.0		24.0		539.7		
				CL				1045.6			
				RT		1342.0			539.7		
STAGE 1C	US 51 RELOCATION 98+50 110+45		LT		1195.0						
				CL	2390.0				48.0		
				RT		1195.0					
STAGE 1	US 51 354+35 360+88 360+88 TR 304 CONNECTOR TR 268 17+63 19+21 19+21	SB	LT				12.0				
				CL	1306.0						
				RT			24.0				
				CL	22.0						
				RT			16.0				
				CL	316.6						
				RT			22.0				
STAGE 2	CROSSOVER "A" 49+80 65+39		LT		1559.4				362.5		
				CL	3118.8				725.0	126	
				RT		1559.4			362.5		
	US 51 344+00 361+30	SB	LT		1729.2						
				CL	3460.0				138		
				RT		1748.2					
	361+30 414+94	SB	LT		5728.2		46.8				
				CL	10812.6			430			
				RT		5430.0					
	414+94 427+50	SB	LT		1533.5		46.8				
				CL	2514.8			100			
				RT		1256.4					
	CROSSOVER "B" 70+00 78+43		LT		842.4				250.0		
CL				1685.5				500.0	68		
RT					842.4			250.0			
TR 268 19+75 22+37		LT		379.3		12.0					
			CL	803.4							
			RT		321.1						
TR 273 17+83 22+17		LT		334.3		12.0					
			CL	722.6							
			RT		340.6		22.0				

STAGE CONSTRUCTION STRIPING SCHEDULE (CONTINUED)

STAGE	STATION TO STATION	LANE	SIDE	PAINT PAVEMENT MARKINGS					PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKERS	PAVEMENT MARKERS REMOVAL
				LINE 5" YELLOW	LINE 5" WHITE	LINE 6" WHITE	LINE 24" WHITE	L & S WHITE			
				FOOT							
STAGE 3	US 51 328+43 361+30	NB	LT		3277.2						
				CL	6563.7					262	
				RT		3555.6			46.8		
	361+30 414+94	NB	LT		5411.7						
				CL	10758.3				428		
				RT		5724.6			46.8		
	414+94 467+10	NB	LT		5243.5						
				CL	10429.9				418		
				RT		5448.2			46.8		
	467+10 521+61	NB	LT		5480.7						
				CL	10905.2				436		
				RT		5687.5			46.8		
	521+61 563+86	NB	LT		4252.9						
				CL	8448.6				338		
				RT		4183.2					
	563+86 567+63	NB	CL		377.0						
				RT		377.0					
				LT	1605.0			46.8			
	572+75 591+05	SB	CL		202.0	260					
				RT	111.0	778					
				LT							
TR 268 20+76 22+37		LT		248.8		12		222.5			
			CL	146.0				34.0			
			RT		247.7		21				
TR 273 17+83 22+17		LT		304.8		22					
			CL	146.0				230.6			
			RT		114.1		12		75.0		
TR 255 / TR 257 47+81 52+18		LT		342.3		22					
			CL	725.7							
			RT		335.9		12				
TR 243 17+83 22+17		LT		334.6		22					
			CL	721.8							
			RT		334.6		12				
CROSSOVER "D" 80+00 88+92		LT		892.0							
			CL	892.0							
STAGE 4 US 51 573+90 591+05	SB	LT						865.1			
			RT					39.0	4		
PROJECT TOTALS				81572.9	82736.3	1038	279	327.6	6305.3	2744	26
USE				164310		1038	279	327.6	6305	2744	26

10/5/2012

D:\01\res\010321\1\SO\TH PLANS NEW\CA00 Sheets\06\2\051-ant-Striping-Schedule.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 SHEET 18 OF 22  
 FAP 322 (US 51)  
 SECTION 11-13  
 CHRISTIAN COUNTY

SCALE: DATE 4/11

DRAWN BY EBB  
 CHECKED BY