F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	45
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STRIPING SCHEDULE

STATION TO STATION		LANE	SIDE	DESCRIPTION	78009005 MODIFIED URETHANE PAVEMENT MARKINGS LINE 5" YELLOW	78009005 MODIFIED URETHANE PAVEMENT MARKINGS LINE 5" WHITE	78009006 MODIFIED URETHANE PAVEMENT MARKINGS LINE 6" WHITE	78009012 MODIFIED URETHANE PAVEMENT MARKINGS LINE 12" YELLOW	X7830072 GROOVING FOR RECESSED PAVEMENT MARKING 6"	X7830074 GROOVING FOR RECESSED PAVEMENT MARKING 7"	78003120 PREFORMED PLASTIC PAVEMENT MARKINGS - TYPE B STANDARD LINE 5" WHITE	78003130 PREFORMED PLASTIC PAVEMENT MARKINGS - TYPE B STANDARD LINE 6" WHITE	78003100 PREFORMED PLASTIC PAVEMENT MARKINGS - TYPE B STANDARD L & S WHITE	78004220 PREFORMED PLASTIC PAVEMENT MARKINGS - TYPE B INLAID LINE 5" WHITE	78004230 PREFORMED PLASTIC PAVEMENT MARKINGS - TYPE B INLAID LINE 6" WHITE	78004240 PREFORMED PLASTIC PAVEMENT MARKINGS - TYPE B INLAID LINE 8" WHITE	78004250 PREFORMED PLASTIC PAVEMENT MARKINGS - TYPE B INLAID LINE 12" WHITE	78004280 PREFORMED PLASTIC PAVEMENT MARKINGS - TYPE B INLAID LINE 24" WHITE	78004200 PREFORMED PLASTIC PAVEMENT MARKINGS - TYPE B INLAID L & S WHITE	78001120 PAINT PVMT MARKINGS LINE 5" YELLOW	78001120 PAINT PVMT MARKINGS LINE 5" WHITE	78100100 RAISED PAVEMENT MARKERS
					FOOT								SQ FT					FOOT			SQ FT				EACH
EX US 51																									
195+32.0	200+31.9		CL	NO-PASSING	999.8				999.8																
200+11.9	200+31.9		LT	EDGE LINE		20.0			20.0																
200+11.9	212+18.9		RT	EDGE LINE		1207.0			1207.0																
200+31.9	212+18.9		CL	EDGE LINE	1187.0				1187.0																
			LT	DIAGONAL				706.2																	
CROSSOVER "A"																									
50+00.0	65+39.4		CL	EDGE LINE	1539.4				1539.4																
			LT	EDGE LINE		1539.4			1539.4																
57+15.1	65+39.4		RT	DIAGONAL				687.2																	
TR 268																									
18+01.2	19+40.9		LT	EDGE LINE																				173.2	
			CL	NO-PASSING/STOP BAR															21.3		240.8				
			RT	EDGE LINE																				222.1	
20+64.8	22+04.5		LT	EDGE LINE																				222.1	
			CL	NO-PASSING/STOP BAR															21.3		240.8				
			RT	EDGE LINE																				173.2	
TR 273																									
17+83.0	19+39.0		LT	EDGE LINE																				194.7	
			CL	NO-PASSING/STOP BAR															21.7		276				
			RT	EDGE LINE																				236.6	
20+61.0	22+17.3		LT	EDGE LINE																				237.3	
			CL	NO-PASSING/STOP BAR															21.7		276.6				
			RT	EDGE LINE																				195	
TR 255																									
47+81.6	49+39.0		LT	EDGE LINE																				195.8	
			CL	NO-PASSING/STOP BAR															21.3		279				
			RT	EDGE LINE																				238.3	
TR 257																									
50+61.0	52+18.4		LT	EDGE LINE																				238.3	
			CL	NO-PASSING/STOP BAR															21.3		279				
			RT	EDGE LINE																				195.8	
TR 243																									
17+82.5	19+39.0		LT	EDGE LINE																				195.1	
			CL	NO-PASSING/STOP BAR															21.6		277				
			RT	EDGE LINE																				237.2	
20+61.0	22+17.5		LT	EDGE LINE																				237.2	
			CL	NO-PASSING/STOP BAR															21.6		277				
			RT	EDGE LINE																				195.1	
SERVICE DRIVE 451 CONNECTOR																									
8+91.0	9+51.0		LT	EDGE LINE																				94.3	
			CL	NO-PASSING/STOP BAR															23.0		60				
			RT	EDGE LINE																				94.3	
SERVICE DRIVE 547 CONNECTOR																									
48+92.8	49+51.0		LT	EDGE LINE																				92.5	
			CL	NO-PASSING/STOP BAR															20.1		56.6				
			RT	EDGE LINE																				92.5	
TOTALS					46890.8	47877.3	283.0	1672.0	95298.1	641.5	100.0	358.5	62.4	11230.0	11252.7	2150.2	860.3	214.9	1161.6	2262.8		3760.6	760		
USE					94769		283	1672	95299	642	100	359	63	11230	11253	2151	861	215	1162	6024			760		

REVISIONS	
NAME	DATE
SEB	10/10/12
SEB	11/7/12

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SHEET 21 OF 22
FAP 322 (US 51)
SECTION 11-13
CHRISTIAN COUNTY

SCALE: DRAWN BY EBB

DATE 4/11 CHECKED BY

11/7/2012

D:\Brian\Q10329\SOUTH PLANS NEW\CADD Sheets\D672961-sht-Schedules.dgn