

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	46
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

LIGHTING SCHEDULE

PAY ITEM	PAY ITEM DESCRIPTION	UNIT	CROSSOVER A & TR 268 INTERSECTION	TR 273 INTERSECTION	TR 255 & TR 257 INTERSECTION	TR 243 INTERSECTION	TOTALS
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	1	1	4
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	180	245	250	250	925
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	50				50
81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT			20		20
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT			170		170
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH			4		4
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	2298	1598	1633	1690	7219
81603065	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO.2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2256				2256
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	117	117	117	117	468
81800185	AERIAL CABLE, 2-1/C NO. 1/0 WITH MESSENGER WIRE	FOOT	1580				1580
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	10	10	10	10	40
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	7				7
82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH		1	1	1	3
82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP	EACH	1				1
83003600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM	EACH	10	10	10	10	40
83057340	LIGHT POLE, WOOD, 60 FOOT, CLASS 3	EACH	8				8
83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	10	10	10	10	40
83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	40	40	40	40	160

REMOVAL OF LIGHTING UNIT, NO SALVAGE
84200600

STATION	SIDE	EACH
FAP 322 (US 51)		
521+37	LT	1
551+84	LT	1
553+84	LT	1
555+84	LT	1
557+84	LT	1
559+84	LT	1
559+84	RT	1
561+84	RT	1
563+84	RT	1
565+84	RT	1
TOTAL		10

REVISIONS	
NAME	DATE
SEB	10/10/12
SEB	11/14/12

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 SHEET 22 OF 22
 FAP 322 (US 51)
 SECTION 11-13
 CHRISTIAN COUNTY

SCALE: DATE 4/11
 DRAWN BY EBB
 CHECKED BY

11/14/2012

G:\01\res\010321\SOJTH PLANS NEW\CAD - Sheets\0672961-ant-Schedule.dgn