

ILLINOIS DEPARTMENT OF TRANSPORTATION			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
SUMMARY OF QUANTITIES				0021					
				SHELBY CO. (172)		MOULTRIE CO. (139)			
CODE NO	ITEM	UNIT		MOHSIP 90% FED. 10% STATE	ACF 80% FED. 20% STATE	MOHSIP 90% FED. 10% STATE	ACF 80% FED. 20% STATE		
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	1334	315	105	685	229		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	27	7	3	13	4		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	174	38	13	92	31		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	13	4	1	6	2		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	42	10	3	22	7		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5063	1195	398	2602	868		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	59269	13984	4661	30468	10156		
50105220	PIPE CULVERT REMOVAL	FOOT	1388	344	115	697	232		
54213450	END SECTIONS 15"	EACH	108	25	9	55	19		
54213453	END SECTIONS 18"	EACH	6			4	2		
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	1659	421	140	823	275		
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	73			55	18		
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	133677	30640	10213	69618	23206		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	1		2	1		

FILE NAME :	USER NAME :	DESIGNED :	REVISED :
c:\pwork\pwidot\teasleyok\0279424\074552-shl-soq.dgn	teasleyok	-	-
Default	PLT SCALE :	CHECKED :	REVISED :
	100.0000 1/4 in.	-	-
	PLOT DATE :	DATE :	REVISED :
	11/16/2012	-	-

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET	OF	SHEETS
STA.	TO STA.		

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
770		**	8	3
			CONTRACT NO. 74552	
ILLINOIS FED. AID PROJECT				