

**BLACK TEMPORARY PAVEMENT MARKING TAPE SCHEDULE**

(STAGE 1)

| SN 058-0077 |    |           |             |             |          |
|-------------|----|-----------|-------------|-------------|----------|
| LOCATION    |    |           | DESCRIPTION | LENGTH      | QUANTITY |
| STA         | TO | STA       |             | (FOOT)      | (FOOT)   |
| 855+13      | TO | 861+36.68 | EDGE LINE   | 623.7       | 623.7    |
| 126+68      | TO | 132+20    | EDGE LINE   | 552.0       | 552.0    |
| 135+70      | TO | 137+99    | EDGE LINE   | 229.0       | 229.0    |
| 137+21      | TO | 144+13    | CENTERLINE  | 692.0       | 173.0    |
|             |    |           |             | TOTAL       | 1578     |
| RAMP        |    |           |             |             |          |
| 135+70      | TO | 136+21.00 | EDGE LINE   | 51.0        | 51       |
|             |    |           |             | TOTAL       | 51       |
| SN 058-0078 |    |           |             |             |          |
| 850+18      | TO | 856+74    | CENTERLINE  | 656         | 164.0    |
| 852+68      | TO | 861+36.68 | EDGE LINE   | 869.2       | 869.2    |
| 126+68      | TO | 135+41    | EDGE LINE   | 873.0       | 873.0    |
|             |    |           |             | TOTAL       | 1742.2   |
|             |    |           |             | GRAND TOTAL | 2022     |

**PAINT PAVEMENT MARKING - LINE 4" SCHEDULE**

SN 058-0073

| LOCATION |    |       | LENGTH | YELLOW | WHITE |
|----------|----|-------|--------|--------|-------|
| STA      | TO | STA   | (FOOT) | FOOT   | FOOT  |
| 70+30    | TO | 73+26 | 296.0  | 370    |       |
| 73+26    | TO | 76+83 | 356.5  | 713    |       |
| 76+83    | TO | 79+93 | 310.5  | 388    |       |
| 71+73    | TO | 78+61 | 688.0  |        | 688   |
| 71+49    | TO | 78+37 | 687.5  |        | 688   |
|          |    |       |        | TOTAL  | 1471  |
|          |    |       |        |        | 1376  |

**BLACK TEMPORARY PAVEMENT MARKING TAPE SCHEDULE**

(STAGE 2)

| SN 058-0077 |    |           |             |             |          |
|-------------|----|-----------|-------------|-------------|----------|
| LOCATION    |    |           | DESCRIPTION | LENGTH      | QUANTITY |
| STA         | TO | STA       |             | (FOOT)      | (FOOT)   |
| 860+13      | TO | 861+36.68 | EDGE LINE   | 123.7       | 123.7    |
| 126+68      | TO | 132+21    | EDGE LINE   | 553.0       | 553.0    |
| 137+21      | TO | 146+21    | CENTERLINE  | 900.0       | 225.0    |
|             |    |           |             | TOTAL       | 902      |
| SN 058-0078 |    |           |             |             |          |
| 127+05      |    | 133+82.0  | EDGE LINE   | 677.0       | 677.0    |
| 846+74      | TO | 856+74    | CENTERLINE  | 1000.0      | 250.0    |
|             |    |           |             | TOTAL       | 927.0    |
|             |    |           |             | GRAND TOTAL | 1829     |

**RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE**

| LOCATION    |    |        |        | LENGTH | REPLACEMENT REFLECTOR | RAISED REFLECTIVE PAVEMENT MARKER REFLECTOR REMOVAL |
|-------------|----|--------|--------|--------|-----------------------|---|
| STA         | TO | STA    | (FOOT) | (EACH) | (EACH)                |   |
| SN 058-0077 |    |        |        |        |                       |   |
| 137+21      | TO | 144+13 | 692.0  | 9      | 9                     |   |
| SN 058-0078 |    |        |        |        |                       |   |
| 580+18      | TO | 586+74 | 656.0  | 9      | 9                     |   |
|             |    |        |        | TOTAL  | 18                    | 18  |

|                                     |                               |            |           |
|-------------------------------------|-------------------------------|------------|-----------|
| FILE NAME =                         | USER NAME = teasleyck         | DESIGNED - | REVISED - |
| c:\pwork\pwork\teasleyck\0307638\07 | 4591-shit-schedules.dgn       | DRAWN -    | REVISED - |
| Default                             | PLOT SCALE = 100.0000' / 1in. | CHECKED -  | REVISED - |
|                                     | PLOT DATE = 10/29/2012        | DATE -     | REVISED - |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

|                  |       |           |              |
|------------------|-------|-----------|--------------|
| <b>SCHEDULES</b> |       |           |              |
| SCALE:           | SHEET | OF SHEETS | STA. TO STA. |

|                           |                          |              |              |           |
|---------------------------|--------------------------|--------------|--------------|-----------|
| F.A. RTE.                 | SECTION                  | COUNTY       | TOTAL SHEETS | SHEET NO. |
| *                         | D7 BRIDGE REPAIRS 2013-3 | MACON        | 28           | 4         |
|                           | *FAI 72, FAU 7354        | CONTRACT NO. | 74591        |           |
| ILLINOIS FED. AID PROJECT |                          |              |              |           |