

# SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL	ACM	ACF	ACM	ACM	ACM	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% STATE 20% CITY	80% FEDERAL 20% STATE	100% STATE
				ROADWAY	ROADWAY	ROADWAY	BICYCLE/PEDS	TRAFFIC SIGNALS	TRAFFIC SIGNALS
				0001	0004	0004	0028	0021	0021
				URBAN	URBAN	URBAN			
				F. A. U. 9324	F. A. P. 312	F. A. U. 9321			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	143	99	44				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	193	193					
20200100	EARTH EXCAVATION	CU YD	23475	10015	12380	1080			
20400800	FURNISHED EXCAVATION	CU YD	19550	14900	4270	380			
20700220	POROUS GRANULAR EMBANKMENT	CU YD	815	815					
20800150	TRENCH BACKFILL	CU YD	1504	603	895	6			
* 25000210	SEEDING, CLASS 2A	ACRE	13.25	7.00	5.25	1.00			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1169	619	471	79			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1169	619	471	79			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1169	619	471	79			
* 25100115	MULCH, METHOD 2	ACRE	11.5	6.0	4.5	1.0			
* 25100630	EROSION CONTROL BLANKET	SO YD	7191	4133	3058				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1299	688	523	88			
28000305	TEMPORARY DITCH CHECKS	FOOT	3650	2025	1575	50			

\*SPECIALTY ITEM

LAST SAVED = 10/11/2012  
 PEN TABLE = VBI-HGT.tbl  
 PLOT DRIVER = PLOTDRIVER.exe

FILE NAME = J:\10011001\Phase II - 76F51\Cad\11_Plans\03_0076F51-shr-500.dgn	USER NAME = jspottis@na	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

HORNER &  
 SHIRIN, INC.  
 ENGINEERS

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 13 SHEETS STA. TO STA.

F.A.U. RTE. 9324	SECTION 68-R-1	COUNTY MONROE	TOTAL SHEETS 192	SHEET NO. 3
CONTRACT NO. 76F51			ILLINOIS FED. AID PROJECT	