

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL	ACM	ACF	ACM	ACM	ACM			
				CONSTRUCTION CODE							
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE ROADWAY	80% STATE 20% CITY BICYCLE/PEDS	80% FEDERAL 20% STATE TRAFFIC SIGNALS	100% STATE TRAFFIC SIGNS		
				0001 URBAN F. A. U. 9324	0004 URBAN F. A. P. 312	0004 URBAN F. A. U. 9321	0028 URBAN	0021 URBAN	0021 URBAN		
28000400	PERIMETER EROSION BARRIER	FOOT	4461	3224	1028	209					
28000500	INLET AND PIPE PROTECTION	EACH	22	12	8	2					
28001100	TEMPORARY EROSION CONTROL BLANKET	SO YD	7191	4133	3058						
28100207	STONE RIPRAP, CLASS A4	TON	984	792	192						
28200200	FILTER FABRIC	SO YD	2482	2345	137						
28300400	AGGREGATE DITCH	TON	1037	1017	20						
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	26391	10894	11700	1675	2122				
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SO YD	16			16					
35501311	HOT-MIX ASPHALT BASE COURSE, 6 3/4"	SO YD	9206		9206						
35501319	HOT-MIX ASPHALT BASE COURSE, 8 3/4"	SO YD	1118			1118					
40200700	AGGREGATE SURFACE COURSE, TYPE A B"	SO YD	2494	1156	406	932					
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.5	1.5		2					
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	10.4	10.4							
40300500	COVER COAT AGGREGATE	TON	43	43							

* SPECIALTY ITEM

LAST SAVED: 10/11/2012 12:02:37 PM
 FILE NAME: I:\10011001_Phase II - 76F51\Cad\TX_Plots
 PLOT DRIVER: pdfplotter.plt

FILE NAME =	USER NAME = jepostibone	DESIGNED -	REVISED -
I:\10011001_Phase II - 76F51\Cad\TX_Plots	03_0876F51-plt-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 2.0000 / in.	CHECKED -	REVISED -
	PLOT DATE = 10/11/2012 12:02:37 PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 13 SHEETS STA. TO STA.

F.A.U. RTE. 9324	SECTION 68-R-1	COUNTY MONROE	TOTAL SHEETS 192	SHEET NO. 4
CONTRACT NO. 76F51			ILLINOIS FED. AID PROJECT	