

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL	ACM	ACF	ACM	CONSTRUCTION CODE		
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE ROADWAY	80% STATE 20% CITY BICYCLE/PEDS	80% FEDERAL 20% STATE TRAFFIC SIGNALS	100% STATE TRAFFIC SIGNS
				0001 URBAN	0004 URBAN	0004 URBAN	0028 URBAN	0021 URBAN	0021 URBAN
				F. A. U. 9324	F. A. P. 312	F. A. U. 9321			
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	19		19				
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	39		39				
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	12		12				
60100915	PIPE DRAINS 6"	FOOT	60	30	20	10			
60100925	PIPE DRAINS 8"	FOOT	60	30	20	10			
60100945	PIPE DRAINS 12"	FOOT	60	30	20	10			
60107600	PIPE UNDERDRAINS 4"	FOOT	5338		5338				
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	212		212				
60220005	MANHOLES, TYPE A, 4' -DIAMETER, WITH MEDIAN INLET (604101)	EACH	2	1	1				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	319.5	146.0	99.0	74.5			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	1367	935		432			
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	8325	6430	1515	380			
61100605	MISCELLANEOUS CONCRETE	CU YD	9.0	4.5	3.0	1.5			
61101007	STORM SEWERS PROTECTED, CLASS A, 6"	FOOT	300	300					

• SPECIALTY ITEM

LAST SAVED = 10/11/2012 12:52:39 PM
 PLOT DRIVER = d:\in\10011800\Phase II - 76F51\Cad\11_Plane
 FILE NAME = 03_0876F51-sh1-500.dgn
 PLOT SCALE = 2,0000 1/ in.
 PLOT DATE = 10/11/2012 12:52:39 PM

FILE NAME =	USER NAME = jepettibone	DESIGNED -	REVISED -
1:\10011800\Phase II - 76F51\Cad\11_Plane	03_0876F51-sh1-500.dgn	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 6 OF 13 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9324	68-R-1	MONROE	192	8
CONTRACT NO. 76F51			ILLINOIS FED. AID PROJECT	