FAU 9324

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL	ACM 80% FEDERAL 20% STATE ROADWAY 0001 URBAN F.A.U. 9324	ACF 80% FEDERAL 20% STATE ROADWAY 0004 URBAN F.A.P. 312	ACM 80% FEDERAL 20% STATE ROADWAY 0004 URBAN F.A.U. 9321	ACM 80% STATE 20% CITY BICYCLE/PEDS 0028 URBAN	ACM 80% FEDERAL 20% STATE TRAFFIC SIGNALS 0021 URBAN	ACM 100% STATE TRAFFIC SIGNS 0021 URBAN
					CONSTRUCTION CODE					
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	800					800	
*	87500900	TRAFFIC SIGNAL POST, 13 FT.	EACH	3					3	
*	87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1					1	
*	87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1					1	
*	87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1					1	
*	87700320	STEEL MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1					1	
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	9					9	
*	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3					3	
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	54					54	
*	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	11					11	
*	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	14					14	
*	88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	4					4	
*	88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	14					14	
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	11					11	

* SPECIALTY ITEM

11

LAST SAVED = 10/11/2012
PEN TABLE = VEs-Half.tbl
PLOT DRIVER = pdfMX.ARESbw.pltcfg

FILE NAME = I:\1001100_Phase II - 76F51\Cad\T_Plans\03_087GF51-sht-SQQ.dgn	USER NAME = jappelibone	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 2.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/11/2012 12:52:42 PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HORNER & SHIFRIN, INC. ENGINEERS

SCALE: NONE

SUMMARY OF QUANTITIES

SHEET NO. 11 OF 13 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9324	68-R-1	MONROE	192	13

CONTRACT NO. 76F51

ILLINOIS FED. AID PROJECT