CODE NUMBER	PAY ITEM	CONSTRUCTION TYPE CODE 0011	
		UNIT	035-0016, FUNDING 80% FEDERAL, 20% STATE
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	1092
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	70,020
50800515	BAR SPLICERS	EACH	630
51201600	FURNISHING STEEL PILES HP12X53	FOOT	777
51202305	DRIVING PILES	FOOT	777
51204650	PILE SHOES	EACH	14
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	28
54215547	METAL END SECTIONS 12"	EACH	1
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	100.3
60100945	PIPE DRAINS 12"	FOOT	21
60500060	REMOVING INLETS	EACH	1
60900515	CONCRETE THRUST BLOCKS	EACH	1

FILE NAME = c:\pw_work\pwidot\kelley.kol\d824233\78152-sht-svr-soq.index.dgn

USER NAME = $USER$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
	DRAWN -	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	
PLOT DATE = 10/17/2012	DATE -	REVISED -	

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	118-1	HARDIN	50	5
		CONTRACT NO. 78152		
		ILLINOIS FED. AID PROJECT		